

SUMMARY OF QUANTITIES

SPECIALTY ITEM	CODE NUMBER	ITEM	UNIT	TOTAL QUANTITY	BIKE/PED TRAILS	ROADWAY	ROADWAY	SAFETY	BRIDGE	WATER MAIN ELEC. DISTRIB.
					CMAQ/ITEP/STP 80/20 0028	100% STATE 0001	100% STATE 0004	100% STATE 0021	0008	100% LOCAL 0043
	4200501	PORTLAND CEMENT CONCRETE PAVEMENT 10" (JOINTED)	SQ YD	7,632		7,632				
	4070 2700	FURNISH PROFILOGRAPH	L SUM	1		1				
	42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	699				699		
	42400800	DETECTABLE WARNINGS	SQ FT	50				50		
	44000100	PAVEMENT REMOVAL	SQ YD	504		504				
	44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	2,400		828	1,572			
	44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	1,823			1,823			
	44000600	SIDEWALK REMOVAL	SQ FT	174			174			
	44004250	PAVED SHOULDER REMOVAL	SQ YD	2,146			2,146			
	44201789	CLASS D PATCHES, TYPE II, 12 INCH	SQ YD	113			113			
	44201815	CLASS D PATCHES, TYPE II, 14 INCH	SQ YD	53			53			
	48101600	AGGREGATE SHOULDERS, TYPE B 8"	SQ YD	1,300			1,300			
	48203021	HOT-MIX ASPHALT SHOULDERS, 6"	SQ YD	359		359				
	48203029	HOT-MIX ASPHALT SHOULDERS, 8"	SQ YD	1,300			1,300			
	48301000	PROTECTIVE COAT	SQ YD	15,264		15,264				
	50105220	PIPE CULVERT REMOVAL	FOOT	215			215			
	50200100	STRUCTURE EXCAVATION	CU YD	756					756	
	50200300	COFFERDAM EXCAVATION	CU YD	1,458	510				948	
	50201121	COFFERDAM (TYPE 2) (LOCATION - 1)	EACH	1					1	
	50201122	COFFERDAM (TYPE 2) (LOCATION - 2)	EACH	1	1					
	50201123	COFFERDAM (TYPE 2) (LOCATION - 3)	EACH	1	1					
	50201124	COFFERDAM (TYPE 2) (LOCATION - 4)	EACH	1					1	
	50201125	COFFERDAM (TYPE 2) (LOCATION - 5)	EACH	1					1	
	50300225	CONCRETE STRUCTURES	CU YD	2457.0	860.0				1,597.0	
	50300255	CONCRETE SUPERSTRUCTURE	CU YD	1465.1					1,465.1	
	50300260	BRIDGE DECK GROOVING	SQ YD	4,860					4,860	
	50300265	SEAL COAT CONCRETE	CU YD	733.6					733.6	
	50300280	CONCRETE ENCASMENT	CU YD	14.2	7.1				7.1	
	50300300	PROTECTIVE COAT	SQ YD	6,139					6,139	
	50500505	STUD SHEAR CONNECTORS	EACH	14,277					14,277	
	50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	733,090	183,280				549,810	
	50800515	BAR SPLICERS	EACH	91					91	
	51201600	FURNISHING STEEL PILES HP12X53	FOOT	2,808					2,808	
	51201800	FURNISHING STEEL PILES HP14X73	FOOT	8,866	3,103				5,763	
	51202305	DRIVING PILES	FOOT	11,674					11,674	
	51203600	TEST PILE STEEL HP12X53	EACH	6					6	

PLOT SCALE: 1:1
 X:\100005\10005\Local\Workspace\P10\BRN\Drawn\PDF\08 FULL SIZE.plt
 X:\100005\10005\Local\Workspace\P10\BRN\Title\08 CCB1

FILE NAME =	DESIGNED - MAC	REVISED -
... \p10\ABC-sh1-soq-02.dgn	DRAWN - TMB	REVISED -
USER NAME = mooleman	CHECKED - RMT	REVISED -
PLOT DATE = 12/8/2011	DATE - 10/23/2011	REVISED -



CITY OF ST. CHARLES

SUMMARY OF QUANTITIES			
SCALE: NTS	SHEET NO. 2 OF 9 SHEETS	STA.	TO STA.

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	04-0092-00-BR	KANE	440	5
CONTRACT NO. 63650			ILLINOIS FED. AID PROJECT	