

REMOVAL SCHEDULE							
ITEM DESCRIPTION	HOT-MIX ASPHALT SURFACE REMOVAL, 2" (SQ. YD)	DRIVEWAY PAVEMENT REMOVAL (SQ. YD)	COMBINATION CURB AND GUTTER REMOVAL (FT.)	PAVED SHOULDER REMOVAL (SQ. YD)	REMOVAL OF EXISTING STRUCTURES	PIPE CULVERT REMOVAL	STORM SEWER REMOVAL, 15"
PAY ITEM NUMBER	44000157	44000200	44000500	44004250	50100100	50105220	55100700
<b>RED GATE ROAD</b>							
BOP TO STA. 98+00.00	989	-	-	89	-	-	-
STA. 98+00.00 TO STA. 104+00.00	792	-	-	127	-	-	-
<b>IL-31</b>							
STA. 202+44.00 TO STA. 207+00.00	1759	-	-	371	-	-	-
STA. 207+00.00 TO STA. 213+00.00	2873	-	-	715	-	-	-
STA. 213+00.00 TO STA. 218+70.00	1860	-	-	656	-	-	-
<b>IL - 25</b>							
STA. 301+40.00 TO STA. 306+00.00	1348	-	921	-	2	-	280
STA. 306+00.00 TO STA. 312+00.00	1797	86.9	890	64	4	51	390
STA. 312+00.00 TO STA. 315+62.00	1116	72.5	-	340	-	100	-

EROSION AND SEDIMENT CONTROL SCHEDULE								
ITEM DESCRIPTION	MULCH, METHOD 2 (ACRE)	TEMPORARY DITCH CHECKS (EACH)	PERIMETER EROSION BARRIER (FOOT)	INLET FILTERS (EACH)	STONE RIPRAP, CLASS A3 (SQ. YD)	STONE RIPRAP, CLASS A4 (SQ. YD)	FILTER FABRIC (SQ. YD)	STABILIZED CONSTRUCTION ENTRANCE (SQ. YD)
PAY ITEM NUMBER	25100115	28000300	28000400	28000510	28100105	28100107	28200200	X0322671
<b>RED GATE ROAD</b>								
BOP TO STA. 98+00.00	0.31	-	-	-	-	-	-	-
STA. 98+00.00 TO STA. 104+00.00	0.52	-	679	5	-	35	-	576
STA. 104+00.00 TO STA. 110+00.00	0.66	-	1231	8	-	-	-	-
STA. 110+00.00 TO STA. 116+00.00	0.24	-	387	-	-	-	-	-
STA. 116+00.00 TO STA. 122+00.00	1.36	-	1242	8	-	-	-	-
STA. 122+00.00 TO STA. 128+00.00	0.27	-	1209	3	-	-	-	576
STA. 128+00.00 TO EOP	0.22	-	814	9	-	-	-	-
<b>IL-31</b>								
STA. 202+44.00 TO STA. 207+00.00	0.73	4	-	-	32	-	-	-
STA. 207+00.00 TO STA. 213+00.00	0.50	7	485	-	-	-	-	-
STA. 213+00.00 TO STA. 218+70.00	0.40	5	1095	-	38	-	-	-
<b>IL - 25</b>								
STA. 301+40.00 TO STA. 306+00.00	0.46	-	649	-	-	27	27	-
STA. 306+00.00 TO STA. 312+00.00	0.77	-	279	7	19	-	-	-
STA. 312+00.00 TO STA. 315+62.00	0.59	-	737	8	57	-	-	-

PLOT SCALE: 1/8" = 1'-0" (1/4" = 1'-0")  
 FILE NAME: ...\\prp1n-abc-sht-schedule-01.dgn  
 USER NAME: tblank  
 PLDT DATE: 11/29/2011

DESIGNED - MAC	REVISED -
DRAWN - TMB	REVISED -
CHECKED - RMT	REVISED -
DATE - 10/23/2011	REVISED -



CITY OF ST. CHARLES

SCHEDULE OF QUANTITIES			
SCALE:	SHEET NO.	OF	TOTAL SHEETS
NTS	1	OF	16 SHEETS

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	04-00092-00-BR	KANE	440	13
CONTRACT NO. 63650			[ILLINOIS] FED. AID PROJECT	