

ROADWAY SCHEDULE						
ITEM DESCRIPTION	SUB-BASE GRANULAR MATERIAL, TYPE B 12" (SQ. YD)	HOT-MIX ASPHALT BASE COURSE, 10" (SQ. YD)	HOT-MIX ASPHALT BASE COURSE, 12" (SQ. YD)	HOT-MIX ASPHALT BASE COURSE WIDENING, 10" (SQ. YD)	HOT-MIX ASPHALT BASE COURSE WIDENING, 12" (SQ. YD)	BITUMINOUS MATERIALS (PRIME COAT) (GALLON)
PAY ITEM NUMBER	31101810	35501324	35501332	35600716	35600724	40300100
RED GATE ROAD						
BOP TO STA. 98+00.00	253	-	-	-	-	114
STA. 98+00.00 TO STA. 104+00.00	3420	-	-	-	-	103
STA. 104+00.00 TO STA. 110+00.00	2414	-	-	-	-	-
STA. 110+00.00 TO STA. 116+00.00	-	-	-	-	-	-
STA. 116+00.00 TO STA. 122+00.00	300	-	-	-	-	-
STA. 122+00.00 TO STA. 128+00.00	2242	-	-	-	-	-
STA. 128+00.00 TO EOP	2944	-	-	-	-	-
IL-31						
STA. 202+44.00 TO STA. 207+00.00	1232	219	-	96	-	265
STA. 207+00.00 TO STA. 213+00.00	1202	1330	-	79	-	619
STA. 213+00.00 TO STA. 218+70.00	1508	-	-	367	-	297
IL - 25						
STA. 301+40.00 TO STA. 306+00.00	690	-	-	-	324	231
STA. 306+00.00 TO STA. 312+00.00	1479	-	1277	-	471	505
STA. 312+00.00 TO STA. 315+62.00	768	-	426	-	60	297

PLOT SCALE: 1/8" = 10' (PDS) FULL SIZE: 11" X 17" (PDS) LOCAL: MicroStation V8i (DRY) (TIT) (ERI) (OCK) (ABI)

FILE NAME =	DESIGNED - MAC	REVISED -
...\\ppln\ABC-sht\schedule-02.dgn	DRAWN - TMB	REVISED -
USER NAME = mcolemn	CHECKED - RMT	REVISED -
PLOT DATE = 11/10/2011	DATE - 10/23/2011	REVISED -



CITY OF ST. CHARLES

SCHEDULE OF QUANTITIES

SCALE: NTS SHEET NO. 2 OF 16 SHEETS STA. TO STA.

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	04-00092-00-BR	KANE	440	14
CONTRACT NO. 63650				
[ILLINOIS] FED. AID PROJECT				