

EARTH EXCAVATION ---- IL 31

STATION	CUT END AREA (SF)	FILL END AREA (SF)	CUT AVERAGE END AREA (SF)	FILL AVERAGE END AREA (SF)	LENGTH (FT)	EXCAVATION (CUT) VOLUME (CU YD)	EMBANKMENT (FILL) VOLUME (CU YD)	CUMULATIVE EXCAVATION VOLUME (CU YD)	CUMULATIVE EMBANKMENT VOLUME (CU YD)
201+50.00	0.02	8.95							
202+00.00	0.00	11.30	0.01	10.13	50.00	0.01	18.75	0.01	18.75
202+50.00	23.20	11.30	11.60	11.30	50.00	21.48	20.93	21.50	39.68
203+00.00	59.00	17.00	41.10	14.15	50.00	76.11	26.20	97.61	65.88
203+50.00	43.50	11.80	51.25	14.40	50.00	94.91	26.67	192.51	92.55
204+00.00	54.40	6.50	48.95	9.15	50.00	90.65	16.94	283.16	109.49
204+50.00	59.20	4.50	56.80	5.50	50.00	105.19	10.19	388.35	119.68
205+00.00	73.00	3.90	66.10	4.20	50.00	122.41	7.78	510.76	127.45
205+50.00	54.40	1.20	63.70	2.55	50.00	117.96	4.72	628.72	132.18
206+00.00	51.20	0.20	52.80	0.70	50.00	97.78	1.30	726.50	133.47
206+50.00	30.90	3.90	41.05	2.05	50.00	76.02	3.80	802.51	137.27
207+00.00	44.50	2.40	37.70	3.15	50.00	69.81	5.83	872.33	143.10
207+50.00	29.60	21.70	37.05	12.05	50.00	68.61	22.31	940.94	165.42
208+00.00	22.10	34.30	25.85	28.00	50.00	47.87	51.85	988.81	217.27
208+50.00	15.00	38.80	18.55	36.55	50.00	34.35	67.69	1023.16	284.95
209+00.00	20.60	76.00	17.80	57.40	50.00	32.96	106.30	1056.13	391.25
209+50.00	41.10	96.90	30.85	86.45	50.00	57.13	160.09	1113.26	551.34

INTERSECTION OMISSION

PLOT SCALE: H: 1/8"=1'-0" V: 1/8"=1'-0" FILE NAME: ... \prpln-ABC-sht-schedule-18.dgn USER NAME: mcoleman PLOT DATE: 11/16/2011

DESIGNED - MAC	REVISED -
DRAWN - TMB	REVISED -
CHECKED - RMT	REVISED -
DATE - 10/23/2011	REVISED -



CITY OF ST. CHARLES

SCHEDULE OF QUANTITIES

SCALE: NTS SHEET NO. 10 OF 16 SHEETS STA. TO STA.

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	04-00092-00-BR	KANE	440	22
CONTRACT NO. 63650			ILLINOIS FED. AID PROJECT	