

EARTH EXCAVATION ---- IL 31

STATION	CUT END AREA (SF)	FILL END AREA (SF)	CUT AVERAGE END AREA (SF)	FILL AVERAGE END AREA (SF)	LENGTH (FT)	EXCAVATION (CUT) VOLUME (CU YD)	EMBANKMENT (FILL) VOLUME (CU YD)	CUMULATIVE EXCAVATION VOLUME (CU YD)	CUMULATIVE EMBANKMENT VOLUME (CU YD)
210+50.00	41.30	84.20							
211+00.00	35.30	49.00	38.30	66.60	50.00	70.93	123.33	1184.18	674.68
211+50.00	31.40	43.30	33.35	46.15	50.00	61.76	85.46	1245.94	760.14
212+00.00	28.00	25.90	29.70	34.60	50.00	55.00	64.07	1300.94	824.21
212+50.00	25.50	21.00	26.75	23.45	50.00	49.54	43.43	1350.48	867.64
213+00.00	28.00	10.20	26.75	15.60	50.00	49.54	28.89	1400.01	896.53
213+50.00	36.30	6.20	32.15	8.20	50.00	59.54	15.19	1459.55	911.71
214+00.00	31.40	3.20	33.85	4.70	50.00	62.69	8.70	1522.24	920.42
214+50.00	40.90	10.80	36.15	7.00	50.00	66.94	12.96	1589.18	933.38
215+00.00	48.30	6.30	44.60	8.55	50.00	82.59	15.83	1671.77	949.21
215+50.00	35.30	2.20	41.80	4.25	50.00	77.41	7.87	1749.18	957.08
216+00.00	24.50	4.30	29.90	3.25	50.00	55.37	6.02	1804.55	963.10
216+50.00	27.40	1.00	25.95	2.65	50.00	48.06	4.91	1852.61	968.01
217+00.00	28.40	2.70	27.90	1.85	50.00	51.67	3.43	1904.27	971.44
217+50.00	27.70	0.80	28.05	1.75	50.00	51.94	3.24	1956.22	974.68
218+00.00	31.50	3.40	29.60	2.10	50.00	54.81	3.89	2011.03	978.56
218+50.00	73.90	2.10	52.70	2.75	50.00	97.59	5.09	2108.63	983.66

PLOT SCALE: 1/4" = 100' (1/8" = 50')
 FILE NAME = ...\\prip1n-abc-sht-schedule-11.dgn
 USER NAME = mcoleman
 PLOT DATE = 11/12/2011

DESIGNED - MAC	REVISED -
DRAWN - TMB	REVISED -
CHECKED - RMT	REVISED -
DATE - 10/23/2011	REVISED -



CITY OF ST. CHARLES

SCHEDULE OF QUANTITIES

SCALE: NTS SHEET NO. 11 OF 16 SHEETS STA. TO STA.

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	04-00092-00-BR	KANE	440	23
CONTRACT NO. 63650			[ILLINOIS] FED. AID PROJECT	