TOPSOIL EXCAVATION AND PLACEMENT ---- IL 31									
STATION	TOPSOIL EXCAVATION END AREA (SF)	TOPSOIL PLACEMENT END AREA (SF)	TOPSOIL EXCAVATION AVERAGE END AREA (SF)	TOPSOIL PLACEMENT AVERAGE END AREA (SF)	LENGTH (FT)	TOPSOIL EXCAVATION (CUT) VOLUME (CU YD)	TOPSOIL PLACEMENT (FILL) VOLUME (CU YD)	CUMULATIVE TOPSOIL EXCAVATION VOLUME (CU YD)	CUMULATIVE TOPSOIL PLACEMENT VOLUME (CU YD)
201+50.00	10.26	6.00							
202+00.00	9.41	5.50	9.84	5.75	50.00	18.21	10.65	18.21	10.65
202+50.00	22.50	11.60	15.96	8.55	50.00	29.55	15.83	47.76	26.48
203+00.00	30.00	16.60	26.25	14.10	50.00	48.61	26.11	96.37	52.59
203+50.00	32.00	17.00	31.00	16.80	50.00	57.41	31.11	153.78	83.70
204+00.00	35.10	15.70	33.55	16.35	50.00	62.13	30.28	215.91	113.98
204+50.00	34.70	15.10	34.90	15.40	50.00	64.63	28.52	280.54	142.50
205+00.00	34.60	14.30	34.65	14.70	50.00	64.17	27.22	344.70	169.72
205+50.00	31.70	11.40	33.15	12.85	50.00	61.39	23.80	406.09	193.52
206+00.00	30.90	9.90	31.30	10.65	50.00	57.96	19.72	464.06	213.24
206+50.00	32.90	9.80	31.90	9.85	50.00	59.07	18.24	523.13	231.48
207+00.00	32.40	10.90	32.65	10.35	50.00	60.46	19.17	583.59	250.65
207+50.00	41.50	14.70	36.95	12.80	50.00	68.43	23.70	652.02	274.35
208+00.00	43.50	15.70	42.50	15.20	50.00	78.70	28.15	730.72	302.50
208+50.00	32.10	11.90	37.80	13.80	50.00	70.00	25.56	800.72	328.06
209+00.00	36.10	14.10	34.10	13.00	50.00	63.15	24.07	863.87	352.13
209+50.00	34.40	8.20	35.25	11.15	50.00	65.28	20.65	929.15	372.78
INTERSECTION OMISSION									
210+50.00	46.60	7.6							
211+00.00	33.00	13.6	39.80	10.60	50.00	73.70	19.63	1002.85	392.41
211+50.00	28.70	13.90	30.85	13.75	50.00	57.13	25.46	1059.98	417.87
212+00.00	33.30	14.40	31.00	14.15	50.00	57.41	26.20	1117.39	444.07
212+50.00	32.40	13.70	32.85	14.05	50.00	60.83	26.02	1178.22	470.09
213+00.00	27.00	10.80	29.70	12.25	50.00	55.00	22.69	1233.22	492.78
213+50.00	21.90	8.00	24.45	9.40	50.00	45.28	17.41	1278.50	510.19
214+00.00	21.20	4.35	21.55	6.18	50.00	39.91	11.44	1318.41	521.62
214+50.00	27.10	8.00	24.15	6.18	50.00	44.72	11.44	1363.13	533.06
215+00.00	29.70	10.40	28.40	9.20	50.00	52.59	17.04	1415.72	550.09
215+50.00	17.80	4.20	23.75	7.30	50.00	43.98	13.52	1459.70	563.61
216+00.00	0.00	0.00	8.90	2.10	50.00	16.48	3.89	1476.19	567.50
216+50.00	11.80	4.80	5.90	2.40	50.00	10.93	4.44	1487.11	571.94
217+00.00	14.90	5.90	13.35	5.35	50.00	24.72	9.91	1511.83	581.85
217+50.00	12.80	4.40	13.85	5.15	50.00	25.65	9.54	1537.48	591.39
218+00.00	10.20	7.20	11.50	5.80	50.00	21.30	10.74	1558.78	602.13
218+50.00	14.30	2.60	12.25	4.90	50.00	22.69	9.07	1581.46	611.20