



- LEGEND**
- EXISTING DOUBLE ACORN LIGHTING UNIT (TO REMAIN)
 - ⊕ PROPOSED DOUBLE ACORN LIGHTING UNIT
 - EXISTING ROADWAY LIGHTING UNIT
 - ⌘ EXISTING LIGHTING UNIT
 - ⊞ EXISTING HANDHOLE

- NOTES:**
1. POLES ARE SET BACK 2' FROM BACK OF CURB TO CENTER OF POLE.
 2. EACH TREE PIT SHALL CONTAIN A DUPLEX WATERPROOF GFI RECEPTICLE WIRED FROM AN ADJACENT LIGHT POLE AS SHOWN.
 3. ALL EXISTING ELECTRIC CABLE IN CONDUIT FOR LIGHT POLES TO BE REMOVED SHALL BE REMOVED AND THE CONDUIT SHALL BE ABANDONED UNLESS UTILIZED FOR ANOTHER CIRCUIT.
 4. CABLE WILL BE RUN TO THE EXISTING STREET LIGHTING CONTROLLER ON THE NORTH SIDE OF THIRD STREET BETWEEN ADDISON AVENUE AND LARCH AVENUE. (SEE LIGHTING WIRING DIAGRAM ON SHEET 15)
 5. A NEW BREAKER WILL BE ADDED TO THE EXISTING CONTROLLER ON THE NORTH SIDE OF THIRD STREET BETWEEN ADDISON AVENUE AND LARCH AVENUE FOR THE ADDITIONAL CIRCUIT.
 6. CONTACT CITY OF ELMHURST ELECTRICAL DIVISION FOR EXACT LOCATIONS AND CIRCUITS.

FILE NAME = g:\od11\0813\road\sheets\LIGHT-283.sht	USER NAME = a_jpondex tar	DESIGNED - KB	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	ELMHURST STREETSCAPE ENHANCEMENTS LIGHTING PLAN ADDISON AVENUE	F.A.I.J. RTE. 2678/2676	SECTION 11-00179-00-LS	COUNTY DUPAGE	TOTAL SHEETS 28	SHEET NO. 13		
PLOT SCALE =	CHECKED - ESN	REVISIED -	SCALE: 1"=20'			SHEET NO. 2 OF 3 SHEETS	STA. 400+44.80 TO STA. 406+45.39	FED. ROAD DIST. NO. 7 ILLINOIS FED. AID PROJECT				
PLOT DATE = 11/16/11	DATE - 11/16/2011	REVISIED -	CONTRACT NO. 63652									