TREE REMOVAL SCHEDULE

STATION	OFFSET	COMMON NAME	(1) CONDITION	(1) FORM	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	TREE REMOVAL (OVER 15 UNITS DIAMETER)	COMMENTS
102+48.54	29.73 LT	white mulberry	2	2	6		
102+74.03	31.6 LT	apple	3	3	12		
104+72.53	37.2 LT	white mulberry	3	3	12		
105+18.89	31.31 LT	honey locust	3	2	12		Deadwood
108+35.24	38.05 LT	black cherry	5	3	14		dead trunk
108+62.77	36.9 LT	boxelder	2	3	14		
108+63.44	41.64 LT	boxelder	2	3	14		
108+95.30	36.54 LT	boxelder	3	3	15		
109+21.30	32.13 LT	boxelder	3	3	12		
109+23.79	36.76 LT	boxelder	3	4	14		lean
109+30.09	42.47 LT	black willow	3	4		22	dead trunk
109+36.23	38.2 LT	boxelder	3	4	12		lean
109+36.47	33.27 LT	boxelder	3	3	14		
109+49.75	46.53 LT	white mulberry	3	3	8		
109+50.64	40.21 LT	boxelder	3	3	12		
109+56.70	40.03 LT	boxelder	3	3	12		
109+66.09	40.91 LT	boxelder	3	3	12		
109+69.72	51.58 LT	boxelder	3	4	14		
109+85.33	51.43 LT	boxelder	3	3	18		
110+22.25	52.03 LT	black cherry	4	3	12		deadwood
110+62.88	41.54 LT	white oak	3	2		26	
110+97.87	39.39 LT	black cherry	3	3	14		
111+27.06	36.85 LT	apple	4	4	10		
111+28.03	46.79 LT	black cherry	3	3	14		
111+53.41	40.01 LT	red cedar	4	3	10		
112+71.09	33.97 LT	white pine	2	2	6		
113+23.28	27.85 LT	white oak	3	3		22	
113+50.83	29.89 LT	white oak	3	3		22	
115+44.90	37.41 LT	white oak	2	3		28	
115+86.97	35.06 LT	hackberry	1	2		16	
116+04.66	41.53 LT	American elm	3	3	8		
116+06.13	30.87 LT	American elm	3	3	6		
116+80.13	31.51 LT	red elm	2	2	10		
117+06.94	32.45 LT	red elm	2	2	8		
117+39.80	35.28 LT	black cherry	3	3	8		
117+57.45	38.49 LT	black cherry	3	3	8		
118+40.74	47.01 LT	white oak	2	2		26	
118+44.99	47.84 LT	red elm	3	3	8		
118+81.43	33.52 LT	white oak	3	2		26	
118+83.93	36.64 LT	hackberry	3	3	10		
119+23.74	45.18 LT	red elm	3	3	8		
119+25.17	38.35 LT	hackberry	2	2	8		
119+62.12	49.74 LT	red elm	3	3	10		
119+83.05	42.08 LT	black cherry	3	3	10		
120+25.59	40.96 LT	walnut	2	1		21	
120+61.25	53.27 LT	walnut	2	2	14		
120+65.05	45.42 LT	red elm	5	5	6		DEAD
120+97.12	56.25 LT	walnut	2	2	14		
121+05.29	51.29 LT	red elm	2	2	9		
121+54.51	49.99 LT	walnut	4	3		24	Deadwood
121+79.90	42.91 LT	honey locust	2	2	12		
124+49.66	33.32 LT	white ash	2	2	8		
124+59.73	36.12 LT	bur oak	2	2		26	
126+20.71	37.75 LT	walnut	3	3	12		
126+64.45	34.61 LT	walnut	3	4	10		
129+84.43	31.1 LT	silver maple	3	3		24	
130+65.67	30.7 LT	walnut	3	3	14		
131+72.58	29.26 LT	walnut	3	2	15		

STATION	OFFSET	COMMON NAME	(1) CONDITION	(1) FORM	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	TREE REMOVAL (OVER 15 UNITS DIAMETER)	COMMENTS
102+14.64	28.83 RT	boxelder	2	3	15		
102+27.08	24.08 RT	black cherry	3	3	14		
102+64.84	20.76 RT	boxelder	5	5	12		DEAD
102+69.00	21.01 RT	black cherry	3	3	12		
102+75.27	20.4 RT	boxelder	5	5	12		DEAD
102+75.37	21.81 RT	black cherry	3	3	12		
102+94.76	20.75 RT	black cherry	5	5	12		DEAD
103+22.62	21.25 RT	boxelder	3	3	12		
103+37.65	19.95 RT	black cherry	3	3	8		
103+48.46	23.79 RT	black cherry	4	3	10		
103+64.81	24.87 RT	boxelder	3	3	10		
103+82.05	22.15 RT	black cherry	2	3	12		
104+84.34	23.57 RT	black cherry	3	3	10		
105+00.47	23.31 RT	American elm	3	3	14		
105+67.14	20.89 RT	black cherry	3	3	10		
105+79.05	20.66 RT	black cherry	3	3	8		
105+96.19	20.53 RT	black cherry	3	3	12		
106+03.25	21.36 RT	black cherry	3	3	12		
106+08.60	22.04 RT	black cherry	3	3	8		
106+13.10	23.11 RT	black cherry	3	3	10		
109+10.44	32.84 RT	boxelder	4	4	8		
120+92.13	27.24 RT	American elm	3	3	8		
129+16.81	39.05 RT	boxelder	3	3	12		
130+88.41	25.96 RT	basswood	3	4	8		
131+38.49	30.74 RT	basswood	3	4	8		topped
131+89.77	22.49 RT	basswood	3	3	6		
132+22.66	29.22 RT	walnut	2	3	12		
132+44.15	22.26 RT	walnut	3	3	15		
132+64.90	30.45 RT	American elm	4	5	6		topped
132+70.47	31.96 RT	American elm	3	3	14		
132+71.22	29.31 RT	basswood	4	4	8		lean
132+79.27	28.21 RT	American elm	4	5	10		topped
132+80.10	38.95 RT	American elm	4	5	10		topped
132+83.30	32.09 RT	boxelder	4	5	10		topped
132+86.00	29.41 RT	boxelder	5	5	10		
133+20.84	27.02 RT	apple	3	3	14		1 tree, 2 stems 6"/8"
133+33.57	45.2 RT	walnut	2	2	15		1 tree not 2
133+35.75	40.88 RT	walnut	3	3	10		1 tree not 2
133+76.90	30.31 RT	walnut	3	3	8		
136+51.74	35 RT	walnut	4	5	8		topped
136+60.39	35.82 RT	walnut	5	5	6		topped
136+74.77	37.29 RT	American elm	4	5	8		topped
136+80.47	34.94 RT	American elm	4	5	8		topped
146+57.64	20.38 RT	red elm	2	2		21	
146+86.01	19.96 RT	sycamore	2	2		24	
147+09.91	20.1 RT	sycamore	1	2		21	
				TOTALS:	**956**	**349**	

NOTES:
(1) SCALE OF 1 TO 5; 1 BEING EXCELLENT AND 5 BEING POOR

CHRISTOPHER B. BURKE ENGINEERING LTD.
9575 West Higgins Road, Suite 600
Rosemont, Illinois 60018
(847) 823-0500

PLAN / PROFILE: SURVEYED, PLOTTED, ALIGNMENT CHECKED, BASES BY, CADD FILE NAME, NOTE BOOK, NO., STRUCTURE NO(S), BY, DATE

FILE NAME = N:\ALGONQUIN\070273.00026\Civil\SCH_070273_2.SHT	USER NAME = mworman	DESIGNED -	REVISED -	**STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION**
	PLOT SCALE = 20'	DRAWN -	REVISED -	**EDGEWOOD DRIVE IMPROVEMENTS SCHEDULE OF QUANTITIES**
	PLOT DATE = 11/15/2011	CHECKED -	REVISED -	SCALE: SHEET NO. OF SHEETS STA. TO STA.
		DATE -	REVISED -	

F.A.U RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
4010	09-00078-00-WR	McHENRY	128	5
		CONTRACT NO. 63655		
		ILLINOIS FED. AID PROJECT		