


NOTES:

1. EXISTING OVERHEAD SIGN STRUCTURE TO BE REMOVED DURING PRE-STAGE.
2. THE RELOCATED SIGN WILL NOT BE LIGHTED DURING CONSTRUCTION OF THIS PROJECT. THE CONTRACTOR SHALL BE RESPONSIBLE FOR STORING THE SIGN LIGHTING CONTROLLER UNTIL SUCH TIME THAT THE SIGN PANELS AND NEW INDUCTION LUMINAIRES CAN BE INSTALLED ON THE NEW STRUCTURE.
3. CONTRACTOR TO INSPECT CONDITION OF SIGN CONTROLLER PRIOR TO REMOVAL FROM EXISTING LOCATION AND REINSTALLATION ON NEW SIGN STRUCTURE.
4. A QUANTITY FOR A NEW HANDHOLE IS INCLUDED. HOWEVER, THE EXISTING HANDHOLE CAN BE RELOCATED IF DIRECTED BY THE ENGINEER.
5. CONDUIT TO BE PUSHED AFTER PROPOSED ROCKTON RD EXIT RAMP IS CONSTRUCTED AND GRADING IS COMPLETED.

LEGEND:

- EXISTING UNIT DUCT
- - - PROPOSED UNIT DUCT
- ⊠ EXISTING LIGHT POLE TO REMAIN UNLESS NOTED OTHERWISE
- ⊠ EXISTING HANDHOLE
- CONDUIT PUSHED, 4" DIA., PVC SCHEDULE 80 (PAID AS UNDERGROUND CONDUIT, PVC, 4" DIA.)
- PROPOSED LIGHT POLE
- ⊠ UNIT DUCT, WITH 2-1/C NO. 2 AND 1/C NO. 8 GROUND, 600V (XLP-TYPE USE), 2" DIA. CNC
- ⊠ PROPOSED HANDHOLE



McClure LOCHNER
Engineering Associates, Inc.
RWA
Engineering Associates, Inc.

USER NAME = USERNAME	DESIGNED - BLM	REVISED -
PLOT SCALE = 50.0000' / IN.	DRAWN - JPW	REVISED -
PLOT DATE = 12/9/2011	CHECKED - BLM	REVISED -
	DATE - 10/14/11	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

**LIGHTING PLAN
OVERHEAD SIGN STRUCTURE**

SCALE:	SHEET NO.	OF	SHEETS	STA.	TO STA.
--------	-----------	----	--------	------	---------

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
90	(X2-1R)	WINNEBAGO	510	275
CONTRACT NO. 64C29				

Rev. 1-9-12

ILLINOIS FED. AID PROJECT