

- SPECIALITY ITEM
- NON-PARTICIPATING ITEM
- 100% WINNEBAGO COUNTY COST

CODE NO.	PAY ITEM	UNIT	URBAN TOTAL QUANTITY	CONSTRUCTION CODES								
				I-90 CONSTRUCTION 90% FEDERAL 10% STATE 0003	BRIDGE SN. 101-0193 90% FEDERAL 10% STATE 0010	BRIDGE SN. 101-0194 90% FEDERAL 10% STATE 0010	BOX CULVERT SN. 101-1095 90% FEDERAL 10% STATE 0040	ROCKTON @ WB I-90 SIGNALS 90% FEDERAL 3.34% STATE 6.66% WINNEBAGO COUNTY 0021	ROCKTON @ EB I-90 SIGNALS 90% FEDERAL 3.34% ISTHA 6.66% WINNEBAGO COUNTY 0021	ISTHA SIGNS 100% ISTHA 0021	WISDOT DMS SIGN 100% WISCONSIN DOT 0021	
X0325734	SLOTTED DRAIN REMOVAL	FOOT	522	522								
• X0326882	VIDEO CAMERA DETECTOR SYSTEM	EACH	2					1		1		
X2070304	POROUS GRANULAR EMBANKMENT, SPECIAL	CU YD	393		210	183						
X4211080	WIDE FLANGE BEAM TERMINAL JOINT COMPLETE (SPECIAL)	EACH	2	2								
X4400100	PORTLAND CEMENT CONCRETE SURFACE REMOVAL (VARIABLE DEPTH)	SQ YD	1579	1579								
X4400110	TEMPORARY PAVEMENT REMOVAL	SQ YD	68860	68860								
X4400600	END SECTIONS TO BE REMOVED	EACH	4	4								
X4401198	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SQ YD	1689	1689								
X4402800	ISLAND PAVEMENT REMOVAL	SQ YD	4	4								
X4402805	ISLAND REMOVAL	SQ FT	650	650								
X5510100	STORM SEWER REMOVAL	FOOT	480	480								
X6015000	REMOVE CONCRETE HEADWALLS FOR PIPE DRAINS	EACH	52	52								
X6050700	REMOVE INLET BOX	EACH	9	9								
X6063401	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-4.12	FOOT	564	564								
X6064201	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-4.06	FOOT	48	48								
X6350120	DELINEATOR REMOVAL	EACH	216	216								
X6380205	TEMPORARY MODULAR GLARE SCREEN	FOOT	3000	3000								
X7010212	TRAFFIC CONTROL AND PROTECTION, STANDARD 701416 (SPECIAL)	EACH	4	4								
X7040650	REMOVE TEMPORARY CONCRETE BARRIER	FOOT	563	563								
• X7240195	REMOVE EXISTING SIGN PANEL	EACH	16								16	
• X7800605	URETHANE PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	242.7	242.7								
• X7800610	URETHANE PAVEMENT MARKING - LINE 4"	FOOT	81383	81383								
• X7800630	URETHANE PAVEMENT MARKING - LINE 6"	FOOT	14568	14568								
• X7800640	URETHANE PAVEMENT MARKING - LINE 8"	FOOT	15449	15449								
• X7800650	URETHANE PAVEMENT MARKING - LINE 12"	FOOT	3799	3799								
• X7800680	URETHANE PAVEMENT MARKING - LINE 24"	FOOT	216	216								
• X7830068	GROOVING FOR RECESSED PAVEMENT MARKING, LETTERS, NUMBERS AND SYMBOLS	SQ FT	110.5	110.5								
• X7830070	GROOVING FOR RECESSED PAVEMENT MARKING 5"	FOOT	67259	67259								
• X7830074	GROOVING FOR RECESSED PAVEMENT MARKING 7"	FOOT	12940	12940								
• X7830076	GROOVING FOR RECESSED PAVEMENT MARKING 9"	FOOT	12470	12470								
• X7830078	GROOVING FOR RECESSED PAVEMENT MARKING 13"	FOOT	3303	3303								
• X7830090	GROOVING FOR RECESSED PAVEMENT MARKING 25"	FOOT	143	143								
• X8950130	MODIFY EXISTING LIGHTING CONTROLLER	EACH	1	1								
X6024875	TEMPORARY INLET	EACH	3	3								
X6020190	DRAINAGE STRUCTURES TYPE 4 SPECIAL WITH TWO TYPE 20 FRAME AND GRATES	EACH	8	8								
X5000015	REMOVE AND REINSTALL PIPE CULVERTS	FOOT	30	30								
• X8410151	TEMPORARY LIGHTING SYSTEM, LOCATION 1	L SUM	1	1								
• X8410152	TEMPORARY LIGHTING SYSTEM, LOCATION 2	L SUM	1	1								
• X8410153	TEMPORARY LIGHTING SYSTEM, LOCATION 3	L SUM	1	1								
• X8410154	TEMPORARY LIGHTING SYSTEM, LOCATION 4	L SUM	1	1								
• X8410155	TEMPORARY LIGHTING SYSTEM, LOCATION 5	L SUM	1	1								



USER NAME = .USERNAME.
 FILE NAME = #FILE#
 PLOT SCALE = 50.0000' / IN.
 PLOT DATE = 11/15/2011
 DESIGNED -
 DRAWN - KRL
 CHECKED - PDS
 DATE - 10-21-2011
 REVISED -
 REVISED -
 REVISED -
 REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES

SCALE: N/A SHEET NO. OF SHEETS STA. TO STA.

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
90	(X2-1) R	WINNEBAGO	510	14
CONTRACT NO. 64C29				
ILLINOIS FED. AID PROJECT				