

0042

- SPECIALITY ITEM
- NON-PARTICIPATING ITEM
- 100% WINNEBAGO COUNTY COST

CODE NO.	PAY ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODES								
				1-90 CONSTRUCTION 90% FEDERAL 10% STATE 0003	BRIDGE SN. 101-0193 90% FEDERAL 10% STATE 0010	BRIDGE SN. 101-0194 90% FEDERAL 10% STATE 0010	BOX CULVERT SN. 101-1095 90% FEDERAL 10% STATE 0010	ROCKTON @ WB I-90 SIGNALS 90% FEDERAL 3.34% STATE 6.66% WINNEBAGO COUNTY 0021	ROCKTON @ EB I-90 SIGNALS 90% FEDERAL 3.34% ISTHA 6.66% WINNEBAGO COUNTY 0021	ISTHA SIGNS 100% ISTHA 0021	WISDOT DMS SIGN 100% WISCONSIN DOT 0021	
J1440010	CONCRETE MEDIAN BARRIER AND BASE REMOVAL	FOOT	374	374								
J1481070	AGGREGATE SHOULDERS SPECIAL, TYPE C	TON	213	213								
J1481110	AGGREGATE SHOULDER WITH FILTER FABRIC, TYPE B	TON	313	313								
J1551010	SLOTTED DRAIN REMOVAL	FOOT	200	200								
J1606050	CONCRETE GUTTER (SPECIAL)	FOOT	15	15								
J1637013	CONCRETE BARRIER BASE, VARIABLE HEIGHT	FOOT	374	374								
J1637014	CONCRETE BARRIER, DOUBLE FACE, VARIABLE HEIGHT	FOOT	374	374								
J5280200	FILTER FABRIC INLET PROTECTION	EACH	2	2								
• JS733090	OVERHEAD SIGN STRUCTURE SPAN TYPE, ALUMINUM 90 FT.	FOOT	90								90	
• JS733105	OVERHEAD SIGN STRUCTURE SPAN TYPE, ALUMINUM 105 FT.	FOOT	105								105	
• JS733210	BRIDGE (CONCRETE) MOUNTED SIGN SUPPORT	FOOT	54								54	
• JS734A10	FOUNDATION FOR OVERHEAD SIGN STRUCTURE, SPAN TYPE	CU YD	95.4								95.4	
• JS814001	HANDHOLE, TOLLWAY	EACH	1	1								
• JS816034	UNIT DUCT, WITH 2-1/2" NO. 8 AND 1/2" NO. 8 GROUND, 600V (XLP-TYPE USE), 2" DIA. ENG COILABLE NONMETALLIC CONDUIT	FOOT	762	762								
• JS816035	UNIT DUCT, WITH 4-1/2" NO. 2 AND 1/2" NO. 8 GROUND, 600V (XLP-TYPE USE), 2" DIA. ENG COILABLE NONMETALLIC CONDUIT	FOOT	387	387								
• JS819001	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	1020	1020								
• JS821003	TEMPORARY LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, 400 WATT	EACH	4	4								
• JS823001	SIGN STRUCTURE WIRING, OVERHEAD SIGN	EACH	2								2	
• JS823003	SIGN STRUCTURE WIRING, BRIDGE MOUNTED SIGN	EACH	1								1	
• JS830027	TEMPORARY WOOD POLE, 50 FT., CLASS 4	EACH	7	7								
• JS842080	REMOVAL OF EXISTING LIGHTING UNIT, SALVAGE	EACH	3	3								
• JS842105	POLE FOUNDATION, REMOVED	EACH	2	2								
• JS846001	MAINTAIN LIGHTING SYSTEM	L SUM	1	1								
JT120330	TEMPORARY SLOTTED DRAIN, 12"	FOOT	200	200								
• JT135061	REAIMING UNITS ← REMOTE TRAFFIC MICROWAVE SENSOR	L SUM	1								1	
• JT720120	SIGN INSTALLATION, TYPE 3	SO FT	1598								1598	
• JT726020	MILEPOST MARKER ASSEMBLY, BARRIER WALL MOUNTED	EACH	26								26	
• JT726050	MILEPOST MARKER INSTALLATION	SO FT	339								339	
• JT736001	REMOVE EXISTING OVERHEAD SIGN STRUCTURE AND FOUNDATION	EACH	2								2	
• JT780300	MULTI-POLYMER PAVEMENT MARKING - LINE 4"	FOOT	7693	7693								
• JT780310	MULTI-POLYMER PAVEMENT MARKING - LINE 6"	FOOT	7376	7376								
• JT821015	REMOVE AND REINSTALL SIGN LUMINAIRE	EACH	15								15	
• JT783005	WATERBLAST PAVEMENT MARKING REMOVAL WITH VACUUM RECOVERY	SO FT	15370	15370								
• Z0076600	TRAINEES	HOUR	2,000	2,000								



USER NAME = JUSERNAME	DESIGNED -	REVISED -
FILE NAME = #FILES#	DRAWN - KRL	REVISED -
PLOT SCALE = 50.0000 "/>		

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES - ISTHA			
F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS
90	(X2-1) R	WINNEBAGO	510
			15

SCALE: N/A	SHEET NO. OF SHEETS	STA. TO STA.	CONTRACT NO. 64C29
(ILLINOIS) FED. AID PROJECT			

Rev.