

**TEMPORARY PAVEMENT MARKINGS / REMOVAL SCHEDULE - CONTINUED**

				70300220	70300250	78001110	78001130	78001140	78001150	70301000	78300100	JT783005
				TEMPORARY PAVEMENT MARKING - LINE 4"	TEMPORARY PAVEMENT MARKING - LINE 8"	PAINT PAVEMENT MARKING - LINE 4"	PAINT PAVEMENT MARKING - LINE 6"	PAINT PAVEMENT MARKING - LINE 8"	PAINT PAVEMENT MARKING - LINE 12"	WORK ZONE PAVEMENT MARKING REMOVAL	PAVEMENT MARKING REMOVAL	WATERBLAST PAVEMENT MARKING REMOVAL WITH VACUUM RECOVERY
STATION	OFF	STATION	OFF	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	SO FT	SO FT	SO FT
5002+33.00	LT	5003+83.00		150								
5002+95.00	CL	5003+83.00		88								
20002+79.07	RT	20004+50.12								58		
20002+79.07	RT	20005+22.99									82	
20002+79.07	LT	20005+53.56									92	
20002+79.07	LT	20006+45.20								123		
20002+79.07	LT	20010+79.79		905								
20002+79.07	RT	20012+64.66		1057								
<b>STAGE 3</b>												
9+00.00		23+00.00		2800						933		
23+00.00		37+00.00		2800						933		
37+00.00		51+00.00		2800						933		
51+00.00		65+00.00		2800						933		
65+00.00		79+00.00		2800						933		
79+00.00		93+00.00		2800						933		
93+00.00		107+00.00		2800						933		
107+00.00		121+00.00		2800						933		
121+00.00		135+00.00		2800						933		
135+00.00		144+00.00		1800						600		
144+00.00		154+00.00		996						332		
981+00.00		995+00.00		330						110		
995+00.00		9+00.00		2570						857		
<b>STAGE 3A</b>												
4995+63.00	RT	5001+39.00		598						200		
4997+69.00	LT	4999+66.00		197						66		
4997+85.00	CL	5001+77.00		392						131		
5001+77.00	CL	5003+22.00		49						17		
5001+87.00	RT	5011+17.00		961						321		
5003+22.00	CL	5010+61.00		739						247		
5004+58.00	LT	5005+93.00									45	
5004+58.00	RT/LT	5011+26.00									446	
5007+76.00	RT	5011+26.00									117	
5010+61.00	CL	5011+43.00		82						28		
5011+23.00	RT	5012+53.00		130						58		
5011+23.00	RT	5012+53.00		172						44		
5011+26.00	RT	5015+48.00									141	
5011+43.00	CL	5015+48.00		405						135		
<b>STAGE 3B</b>												
4995+65.00	RT	5001+91.00		626						209		
4997+70.00	LT	5001+91.00		421						141		
4998+63.00	LT	5001+12.00		285						95		
5000+01.00	LT	5001+00.00		33						11		
5000+86.00	RT	5002+05.00		40						14		
5001+00.00	LT	5001+72.00		72						24		
5002+02.00	LT	5002+84.00		82						28		
5002+05.00	RT	5004+16.00		211						71		
5002+43.00	RT	5004+16.00		173						58		
5003+25.00	RT	5004+16.00									31	
5009+90.00	RT	5010+91.00		101						34		
5009+90.00	LT	5010+96.00		106						36		
5009+90.00	LT	5010+99.00									37	
5009+90.00	RT	5011+04.00		114						38		
5009+90.00	RT	5011+28.00									46	
5010+96.00	LT	5011+97.00		34						12		
5011+04.00	RT	5012+48.00		48						16		
5011+22.00	LT	5016+56.00		534						178		
5011+22.00	RT	5016+56.00		534						178		
5011+45.00	LT	5016+56.00									171	
5011+45.00	RT	5016+56.00									171	
5011+97.00	LT	5016+56.00		459						153		
5012+08.00	LT	5016+56.00									150	
5012+32.00	RT	5016+56.00									142	
5012+48.00	RT	5016+56.00		408						136		
<b>TOLLWAY</b>												
<b>PLACE WINTER SHUTDOWN MARKINGS</b>												
134+20.40		153+44.00				4830		2462				
153+44.00		213+00.00						3529				
<b>EXISTING REMOVAL</b>												
134+20.40		153+44.00										2716
153+44.00		213+00.00										1765
<b>STAGE 1 REMOVAL</b>												
153+44.00		213+00.00										2020
<b>WINTER SHUTDOWN REMOVAL</b>												
134+20.40		153+44.00										5084
153+44.00		213+00.00										1765
<b>STAGE 3 REMOVAL</b>												
153+44.00		213+00.00										2020
<b>TOTAL</b>												
				279879	2750	63378	17451	16910	2658	87918	36950	15370



USER NAME = .\USERNAME.  
 FILE NAME = #FILE#  
 PLOT SCALE = 50.0000' / IN.  
 PLOT DATE = 10/20/2011

DESIGNED -  
 DRAWN - KRL  
 CHECKED - PDS  
 DATE - 10-21-2011

**STATE OF ILLINOIS**  
**DEPARTMENT OF TRANSPORTATION**

**SCHEDULE OF QUANTITIES**  
 SCALE: N/A    SHEET NO. OF SHEETS    STA. TO STA.

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
90	(X2-1) R	WINNEBAGO	510	55
CONTRACT NO. 64C29				
ILLINOIS FED. AID PROJECT				