


NOTES:

1. EXISTING OVERHEAD SIGN STRUCTURE TO BE REMOVED DURING PRE-STAGE.
2. THE RELOCATED SIGN WILL NOT BE LIGHTED DURING CONSTRUCTION OF THIS PROJECT. THE CONTRACTOR SHALL BE RESPONSIBLE FOR STORING THE SIGN LIGHTING LUMINAIRES AND CONTROLLER UNTIL SUCH TIME THAT THE SIGN PANELS AND LUMINAIRES CAN BE REINSTALLED ON THE NEW STRUCTURE.
3. CONTRACTOR TO INSPECT CONDITION OF SIGN LUMINAIRES AND CONTROLLER PRIOR TO REMOVAL FROM EXISTING LOCATION AND REINSTALLATION ON NEW SIGN STRUCTURE.
4. PROVIDING SERVICE FOR THE CONTROLLER IS NOT INCLUDED THIS CONTRACT. THEREFORE, THE CONTROLLER AND SIGN LIGHTS SHALL BE REINSTALLED BUT NOT ENERGIZED UNLESS DIRECTED BY ISTHA.

LEGEND:

- EXISTING UNIT DUCT
- PROPOSED UNIT DUCT
- ⊠ EXISTING LIGHT POLE TO REMAIN UNLESS NOTED OTHERWISE
- PROPOSED LIGHT POLE



USER NAME = .USERNAME.	DESIGNED - BLM	REVISED -
	DRAWN - JPW	REVISED -
PLOT SCALE = 50.0000' / IN.	CHECKED - BLM	REVISED -
PLOT DATE = 10/19/2011	DATE - 10/14/11	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

**LIGHTING PLAN
OVERHEAD SIGN STRUCTURE**

SCALE:	SHEET NO.	OF	SHEETS	STA.	TO STA.
--------	-----------	----	--------	------	---------

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
90	(X2-1)R	WINNEBAGO	510	275
CONTRACT NO. 64C29				
ILLINOIS FED. AID PROJECT				