


NOTES:

1. THE CONTRACTOR SHALL REMOVE TEMPORARY LIGHT POLES, FOLLOWING THE RE-INSTALLATION OF EXISTING POLE AT STA. 145+96.44. ALL WORK ASSOCIATED WITH THIS NOTE SHALL BE INCLUDED IN A COST OF PAY ITEM "MAINTAIN LIGHTING SYSTEM".
2. TIE INTO EXISTING 4" CONDUIT USING AN EXPANSION/DEFLECTION COUPLING.
3. THE CONTRACTOR SHALL RELOCATE EXISTING LIGHT POLE TO ITS ORIGINAL LOCATION.
4. SEE SHEET 282 FOR EXISTING POLE FOUNDATION STRADDLED CAISSON DETAIL AND INFORMATION REGARDING RE-INSTALLATION OF EXISTING LIGHT POLE.
5. TIE NEW UNIT DUCT IN AT EXISTING LIGHTING UNITS AT STATIONS 144+06.44 AND 147+85.44 AND RE-INSTALLED LIGHTING UNIT AT STA. 145+96.44.

LEGEND:

- EXISTING LIGHT POLE TO BE REINSTALLED
- PROPOSED UNIT DUCT
- EXISTING LIGHT POLE TO REMAIN UNLESS NOTED OTHERWISE
- EXISTING LIGHTING CONTROLLER
- UNIT DUCT, WITH 4-1/2" NO. 2 AND 1/2" NO. 8 GROUND, 600V (XLP-TYPE USE) 2" DIA. CNC



| | | | |
|--|-----------------------------|-----------------|-----------|
| | USER NAME = .USERNAME. | DESIGNED - BLM | REVISED - |
| | PLOT SCALE = 50.0000' / IN. | DRAWN - JPW | REVISED - |
| | PLOT DATE = 10/19/2011 | CHECKED - BLM | REVISED - |
| | | DATE - 10/14/11 | REVISED - |

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

**I-90 LIGHTING PLAN
TOLLWAY CROSSOVER**

SCALE: SHEET NO. OF SHEETS STA. TO STA.

| | | | | |
|--------------------|--------------------|---------------------|---------------------------|------------------|
| F.A.I. RTE. 90 | SECTION (X2-1)R | COUNTY WINNEBAGO | TOTAL SHEETS 510 | SHEET NO. 276 |
| CONTRACT NO. 64C29 | | | ILLINOIS FED. AID PROJECT | |