

## INDEX OF SHEETS

1	COVER SHEET
2	INDEX OF SHEETS, STANDARDS, AND COMMITMENTS
3	GENERAL NOTES
4 - 12	SUMMARY OF QUANTITIES
13 - 23	TYPICAL SECTIONS
24 - 40	SCHEDULE OF QUANTITIES
41 - 45	ALIGNMENT, TIES, AND BENCHMARKS
46 - 57	EXISTING CONDITION AND REMOVAL PLAN
58 - 81	US ROUTE 34 PLAN AND PROFILE
82 - 88	CROSS ROAD PLAN AND PROFILE
89 - 154	SUGGESTED MAINTENANCE OF TRAFFIC
155 - 159	DRAINAGE SCHEDULES
160 - 188	DRAINAGE PLAN AND PROFILE
189 - 191	DRAINAGE DETAILS
192 - 193	SUBSURFACE UTILITY ENGINEERING TEST HOLES
194 - 202	RIGHT OF WAY PLANS
203 - 207	EROSION CONTROL AND LANDSCAPING PLANS
208 - 214	INTERSECTION DETAILS
215 - 219	PAVEMENT MARKING PLANS
220 - 225	SIGNING PLANS
226 - 250	TRAFFIC SIGNAL & LIGHTING PLANS
251 - 293	STRUCTURE PLANS - BIG ROCK CREEK BRIDGE
294 - 306	STRUCTURE PLANS - RETAINING WALL 1 SN 047-8800
307 - 317	STRUCTURE PLANS - RETAINING WALL 2 SN 047-8801
318 - 323	STRUCTURE PLANS - PRECAST CONC. BOX CULVERT 1 SN 047-2559
324 - 328	STRUCTURE PLANS - PRECAST CONC. BOX CULVERT 2 SN 047-2541
329 - 342	DISTRICT DETAILS
343	SUPERELEVATION TRANSITION DETAIL
344 - 421	US 34 CROSS SECTIONS
422 - 427	NEEDHAM ROAD CROSS SECTIONS
428	MITCHELL DRIVE CROSS SECTIONS
429	TURNER AVENUE CROSS SECTIONS

## STATE STANDARDS

000001-06	STANDARD SYMBOLS, ABBREVIATIONS AND PATTERNS
001006	DECIMAL OF AN INCH AND OF A FOOT
280001-06	TEMPORARY EROSION CONTROL SYSTEMS
420001-07	PAVEMENT JOINTS
420101-04	24' (7.2m) JOINTED PCC PAVEMENT
420106-04	36' (10.8m) JOINTED PCC PAVEMENT
424001-06	CURB RAMPS FOR SIDEWALKS
420401-08	BRIDGE APPROACH PAVEMENT CONNECTOR
482001-02	HMA SHOULDER ADJACENT TO FLEXIBLE PAVEMENT
515001-03	NAME PLATES FOR BRIDGES
542301-03	PRECAST REINFORCED CONCRETE FLARED END SECTION
542306-02	PRECAST REINFORCED CONCRETE ELLIPTICAL FLARED END SECTION
542311-03	GRATING FOR CONCRETE FLARED END SECTION
542501-02	INLET BOX TYPE 24 (600) A
601001-04	SUB-SURFACE DRAINS
601101-01	CONCRETE HEADWALL FOR PIPE DRAIN
602001-02	CATCH BASIN TYPE A
602301-03	INLET - TYPE A
602306-03	INLET - TYPE B
602401-03	MANHOLE TYPE A
602406-05	MANHOLE TYPE A 6' (1.8 m) DIAMETER
602601-02	PRECAST REINFORCED CONCRETE FLAT SLAB TOP
602701-02	MANHOLE STEPS
604001-03	FRAME AND LIDS TYPE 1
604006-04	FRAME AND GRATE TYPE 3
604016-02	FRAME AND GRATE TYPE 4
604036-02	GRATE TYPE 8
606001-04	CONCRETE CURB TYPE B AND COMBINATION CURB AND GUTTER
606301-04	PC CONCRETE ISLANDS AND MEDIANS
606306-03	CORRUGATED PC CONCRETE MEDIANS
630001-10	STEEL PLATE BEAM GUARDRAIL
630301-05	SHOULDER WIDENING FOR TYPE 1 (SPECIAL) GUARDRAIL TERMINALS
631031-10	TRAFFIC BARRIER TERMINAL, TYPE 6
635006-03	REFLECTOR AND TERMINAL MARKER PLACEMENT
635011-02	REFLECTOR MARKER AND MOUNTING DETAILS
664001-02	CHAIN LINK FENCE
701006-03	OFF-ROAD OPERATIONS, 2L, 2W, 4.5m (15') AWAY TO 600mm (24") FROM EDGE OF PAVEMENT
701206-03	LANE CLOSURE, 2L, 2W, NIGHT ONLY, FOR SPEEDS >= 45 MPH
701601-07	URBAN LANE CLOSURE, MULTILANE, 1W OR 2W WITH NONTRAVERSABLE MEDIAN
701602-05	URBAN LANE CLOSURE, MULTILANE, 2W WITH BIDIRECTIONAL LEFT TURN LANE
701606-08	URBAN LANE CLOSURE, MULTILANE, 2W WITH MOUNTABLE MEDIAN
701701-08	URBAN LANE CLOSURE, MULTILANE INTERSECTION
701901-02	TRAFFIC CONTROL DEVICES
704001-07	TEMPORARY CONCRETE BARRIER
720001-01	SIGN PANEL MOUNTING DETAILS
720006-03	SIGN PANEL ERECTION DETAILS
720011-01	METAL POSTS FOR SIGNS, MARKERS & DELINEATORS
728001-01	SIGN SUPPORT, TELESCOPING STEEL
729001-01	POSTS, METAL APPLICATIONS FOR TYPE A AND B
731001-01	SIGN SUPPORT, TELESCOPING STEEL BASE
780001-03	TYPICAL PAVEMENT MARKINGS
814001-02	HANDHOLES
814006-02	DOUBLE HANDHOLES
857001-01	STANDARD PHASE DESIGNATION DIAGRAMS AND PHASE SEQUENCES
862001-01	UNINTERRUPTIBLE POWER SUPPLY (UPS)
873001-02	TRAFFIC SIGNAL GROUNDING & BONDING
877011-05	STEEL COMB. MAST ARM ASSEMBLY AND POLE 16 FT THROUGH 55 FT
878001-09	CONCRETE FOUNDATION DETAILS
880001-01	SPAN WIRE MOUNTED SIGNALS AND FLASHING BEACON INSTALLATION
880006-01	TRAFFIC SIGNAL MOUNTING DETAILS - POST AND BRACKET MOUNTED
886001-01	DETECTOR LOOP INSTALLATIONS

## COMMITMENTS

- STRUCTURE NOS. 047-0088, 047-2559, 047-2411 ARE RESTRICTED TO LEGAL LOADS ONLY.
- ONE LANE IN EACH DIRECTION MUST REMAIN OPEN DURING PEAK TRAFFIC HOURS.
- NO TREE CLEARING WILL OCCUR BETWEEN APRIL 15 AND SEPTEMBER 1 AT SN 047-0051 (BIG ROCK CREEK).
- NO IN-STREAM WORK IN BIG ROCK CREEK BETWEEN MARCH 1 AND MAY 31. SPAWNING PERIOD OF GREATER REDHORSE.

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION  
DISTRICT THREE


REVIEWED BY: Don Beaul  
DISTRICT STUDIES & PLANS ENGINEER

DATE: 10-25-11

EXAMINED BY: [Signature]  
DISTRICT CONSTRUCTION ENGINEER

[Signature]  
DISTRICT MATERIALS ENGINEER

[Signature]  
DISTRICT OPERATIONS ENGINEER

 <b>PB Americas, Inc.</b> 230 WEST MONROE STREET, SUITE 900 CHICAGO, IL, 60606 (312)782-8150	FILE NAME = D365985-shr-Index-gennote.dgn	DESIGNED - MMS	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	INDEX OF SHEETS, STANDARDS, AND COMMITMENTS			F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	PLOT SCALE =	DRAWN - MMS	REVISED -		SCALE:	STDS 1 OF 1	STA. TO STA.	591	13R-2+14R-1 & BR-1(1)+15R-1	KENDALL	429	2
	PLOT DATE = 19-AUG-2011 08:10	CHECKED - KJB	REVISED -				FINAL SUBMITTAL CONTRACT NO. 66985					
		DATE - 08-18-2011	REVISED -				ILLINOIS FED. AID PROJECT					