


URBAN

SUMMARY OF QUANTITIES

SPECIALTY ITEM	SPECIAL PROV.	CODE NO.	DESCRIPTION	UNIT	TOTAL QUANTITY	FED =80%	FED =80%	FEDERAL = 80%					FED =80%	FEDERAL = 80%	FED =80%	FEDERAL = 0%
						STATE = 20%	STATE = 0%	STATE = 20%					STATE = 10%	STATE = 13.4%	STATE = 20%	STATE = 0%
						CITY = 0%	CITY = 20%	CITY = 0%					CITY = 10%	CITY = 6.6%	CITY = 0%	CITY = 100%
						ROADWAY	NEW SIDEWALK & SHARED USE PATH	STRUCTURAL			WAUBONSEE DR TRAFFIC SIGNAL	MITCHELL DR TRAFFIC SIGNAL	LAKWOOD SPRINGS DR TRAFFIC SIGNAL	SIGNAL INTER-CONNECT	EMERGENCY VEHICLE PRE-EMPTION	HIGHWAY LIGHTING
		0003	0028	0040	0040	0013	0040	0040		0021		0021	0021			
△		88800100	PEDESTRIAN PUSH-BUTTON	EACH	16								4	6	6	
△		89000100	TEMPORARY TRAFFIC SIGNAL INSTALLATION	EACH	3	3										
△		89500100	RELOCATE EXISTING SIGNAL HEAD	EACH	3								3			
△	*	89502375	REMOVE EXISTING TRAFFIC SIGNAL EQUIPMENT	EACH	3								1	1	1	
△	*	89502380	REMOVE EXISTING HANDHOLE	EACH	18								3	3	12	
△	*	89502385	REMOVE EXISTING CONCRETE FOUNDATION	EACH	10									5	5	
	*	X0323260	SEDIMENT BASIN	EACH	20	20										
	*	X0323265	REMOVE EXISTING RIPRAP	SQ YD	98	98										
	*	X0324043	GRATING FOR CONCRETE HEADWALL	EACH	2											
	*	X0325751	DRIVING SOLDIER PILES	FOOT	2,324			1,376	948							
△	*	X0325938	TEMPORARY WIRELESS INTERCONNECT, COMPLETE	L SUM	1										1	
	*	X2070304	POROUS GRANULAR EMBANKMENT, SPECIAL	CU YD	336					150	101	85				
	*	X4060995	TEMPORARY RAMP, SPECIAL	SQ YD	475	475										
	*	X4401198	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SQ YD	1,056	1,056										
	*	50201121	COFFERDAM (TYPE 2) (LOCATION 1)	EACH	1					1						
	*	50201122	COFFERDAM (TYPE 2) (LOCATION 2)	EACH	1					1						
	*	50201123	COFFERDAM (TYPE 2) (LOCATION 3)	EACH	1					1						
	*	50201124	COFFERDAM (TYPE 2) (LOCATION 4)	EACH	1					1						
	*	50800530	MECHANICAL SPLICERS	EACH	16					16						
	*	X6013600	PIPE UNDERDRAINS 4" (MODIFIED)	FOOT	4,083	4,083										
	*	X6020096	MANHOLES, TYPE A, 6'-DIAMETER, WITH 2 TYPE 1 FRAME, CLOSED LID, RESTRICTOR PLATE	EACH	3	3										
	*	X6026400	MANHOLES, DROP TYPE, 4'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	1	1										
	*	X6026600	MANHOLES, DROP TYPE, 6'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	4	4										
	*	X6060714	CONCRETE MEDIAN (SPECIAL)	SQ FT	342	342										
	*	X6061460	PAVED DITCH (SPECIAL)	FOOT	430	430										
	*	X6650202	WOVEN WIRE FENCE REMOVAL	FOOT	1,508	1,508										
△	*	X7830076	GROOVING FOR RECESSED PAVEMENT MARKING 9"	FOOT	2,478	2,478										
△	*	X8730250	ELECTRIC CABLE IN CONDUIT NO. 20 3/C, TWISTED, SHIELDED	FOOT	1170											1170
△	*	X8950115	RELOCATE LIGHT DETECTOR	EACH	1											1
	*	Z0001050	AGGREGATE SUBGRADE 12"	SQ YD	4,571	4,571										
	*	Z0001058	AGGREGATE SUBGRADE 18"	SQ YD	6,304	6,304										
	*	Z0004552	APPROACH SLAB REMOVAL	SQ YD	160					160						
△	*	Z0007118	UNTREATED TIMBER LAGGING	SQ FT	2,988			1,935	1,053							
		Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1										
	*	Z0016200	DECK SLAB REPAIR (PARTIAL)	SQ YD	2					2						
		Z0018002	DRAINAGE SCUPPERS, DS-11	EACH	6					6						

c:\p\work\p\udst\duncanbd\021425\0366985-SHT-500-rev.usd.dgn



FILE NAME = duncanbd
 DESIGNED - MWS
 DRAWN - MWS
 CHECKED - KJB
 DATE - 08-18-2011

REVISED - BDD 10-19-2011
 REVISED -
 REVISED -
 REVISED -

PLOT SCALE = 28.8000' / 1" / in.
 PLOT DATE = 10/19/2011

STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: SQ - 8 OF 9 STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
591	13R-2;14R-1 & BR-1(1);15R-1	KENDALL	429	11
FINAL SUBMITTAL		CONTRACT NO. 66985		
ILLINOIS FED. AID PROJECT				