


- LEGEND**
- ① TEMP PVMT MARKING, LINE 4" (WHITE)
  - ② TEMP PVMT MARKING, LINE 4" (YELLOW)
  - ③ TEMP PVMT MARKING, LINE 4" (DOUBLE YELLOW)
  - ④ TEMP PVMT MARKING, LINE 12" (YELLOW)
  - ⑤ TEMP PVMT MARKING, LINE 8" (WHITE)
  - ⑥ TEMP PVMT MARKING, LINE 8" (2' DASH-6' SKIP WHITE)
  - ⑦ TEMP PVMT MARKING, LINE 24" (WHITE)
  - VERTICAL PANELS AT 50' SPACING IN CURVES AND 100' SPACING IN TANGENTS
  - DRUMS W/ STEADY BURN LIGHTS AT 25' C-C IN TAPERS AND 50' C-C IN TANGENTS
  - ▨ WORK ZONE
  - ▨ TEMPORARY PAVEMENT (HMA BINDER IL-19mm) 9"
  - ↑ TRAFFIC FLOW ARROW
  - TEMPORARY CONCRETE BARRIER
  - ↑ SIGN
  - ▬ BARRICADE TYPE III WITH FLASHING MONODIRECTIONAL LIGHTS
  - ARROW BOARD
  - ▨ SAND MODULE IMPACT ATTENUATOR, TEMPORARY (11 EACH)
  - ▨ TEMPORARY SEEDING
  - ▨ EROSION CONTROL BLANKET
  - ▨ SEDIMENTATION BASIN
  - ⑧ PAVEMENT PATCHES



**PB Americas, Inc.**  
230 WEST MONROE STREET,  
SUITE 900  
CHICAGO, IL 60606  
(312) 782-8150

FILE NAME = NEEDHAMno1a21A.dgn	DESIGNED - DM	REVISED -
PLOT SCALE = 50	DRAWN - MMS	REVISED -
PLOT DATE = 19-AUG-2011 08:17	CHECKED - KJB	REVISED -
	DATE - 08-18-2011	REVISED -

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

**SUGGESTED MAINTENANCE OF TRAFFIC  
NEEDHAM RD - STAGE IA**

SCALE: 1" = 50' MOT - 27 OF 66 STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
591	13R-2(14R-1 & BR-1(1)15R-1	KENDALL	429	115
FINAL SUBMITTAL			CONTRACT NO. 66985	
[ILLINOIS] FED. AID PROJECT				