



**SCHEDULE OF QUANTITIES
ITS FIBER (IL 8 FROM ILLINI DRIVE TO CAMPUS AVE.)**

PORTLAND CEMENT CONCRETE SIDEWALK 4 INCH	SQ FT	25.0
SIDEWALK REMOVAL	SQ FT	25.0
SERVICE INSTALLATION, TYPE B	EACH	1.0
UNDERGROUND CONDUIT, PVC, 2" DIA.	FOOT	300.0
ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO. 6	FOOT	946.5
CONCRETE FOUNDATION, TYPE E 36 INCH DIAMETER	FOOT	14.5
DRILL EXISTING HANDHOLE	EACH	1.0
CAMERA POLE, 45 FT	EACH	1.0
POLE MOUNTED EQUIPMENT CABINET, TYPE B	EACH	1.0
CAT 5 ETHERNET CABLE	FOOT	40.0
CLOSED-CIRCUIT TELEVISION DOME CAMERA, IP BASED	EACH	1.0
FIBER OPTIC CABLE IN CONDUIT, NO. 62.5/125, MM12F SM24F	FOOT	9321.0

FILE NAME = USER NAME = hovelder
 Plans\68370 - IL 8 ITS Fiber Plans (Final 10-2-2011)
 PLOT SCALE = 75.0000' / 1" / 100'
 PLOT DATE = 10/25/2011

DESIGNED -
 DRAWN -
 CHECKED -
 DATE -

REVISED -
 REVISED -
 REVISED -
 REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

**PROPOSED FIBER OPTIC CABLE INSTALLATION
IN EXISTING CONDUIT AND COMMUNICATION VAULTS**

SCALE: NONE ITS FIBER SHEET 2 OF 13 STA. _____ TO STA. _____

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
399	36R-7	TAZEWELL	390	263
CONTRACT NO. 68370				
ILLINOIS FED. AID PROJECT				