INDEX OF SHEETS

SHEET NO.	DESCRIPTION
1	COVER SHEET
2	INDEX OF SHEETS
2	LIST OF STANDARDS
2	GENERAL NOTES
2	COMMITMENTS
3	SUMMARY OF QUANTITIES
4 - 6	GENERAL PLAN - KIRBY AVENUE
7	GENERAL PLAN & ELEVATION
8	DECK CROSS SECTIONS
9	BRIDGE DECK WEARING SURFACE PLAN
10	SUPERSTRUCTURE REPAIR PLAN
11	AS-BUILT PATCHING PLAN
12	JOINT & DRAIN REPAIR DETAILS
13	DECK DRAIN EXTENSION DETAIL
14	STEEL RAILING DETAIL
15 - 21	AS-BUILT PLANS; SN 010-0103 (FOR INFORMATION ONLY)
22	TC&P DEVICES (ROAD & SIDEROAD/STREET CLOSURES)
23 - 27	DETOUR SIGNING

LIST OF HIGHWAY STANDARDS

STANDARD NO.	DESCRIPTION
000001-06	STANDARD SYMBOLS, ABBREVIATIONS AND PATTERNS
001001-02	AREAS OF REINFORCEMENT BARS
001006	DECIMAL OF AN INCH AND OF A FOOT
630001-10	STEEL PLATE BEAM GUARDRAIL
630301-05	SHOULDER WIDENING FOR TYPE 1 (SPECIAL) GUARDRAIL TERMINALS
631032-07	TRAFFIC BARRIER TERMINAL, TYPE 6A
635006-03	REFLECTOR AND TERMINAL MARKER PLACEMENT
635011-02	REFLECTOR MARKER AND MOUNTING DETAILS
701101-02	OFF-ROAD OPERATIONS, MULTILANE, 4.5m (15') TO 600mm (24") FROM PAVEMENT EDGE
701106-02	OFF-ROAD OPERATIONS, MULTILANE, MORE THAN 4.5m (15') AWAY
701400-05	APPROACH TO LANE CLOSURE, FREEWAY/EXPRESSWAY
701406-06	LANE CLOSURE, FREEWAY/EXPRESSWAY, DAY OPERATIONS ONLY
701901-02	TRAFFIC CONTROL DEVICES
780001-03	TYPICAL PAVEMENT MARKINGS

GENERAL NOTES

GENERAL NOTES

G.N.-100

ENGLISH UNITS OF MEASUREMENT SHALL GOVERN OVER AND SUPERSEDE ANY METRIC UNITS SHOWN IN THIS CONTRACT. WHERE INCLUDED, METRIC UNITS ARE FOR INFORMATION ONLY.

G.N.-100A

ELECTRONIC FILES AND/OR ELECTRONIC SURVEY INFORMATION INCLUDING CADD FILES WILL NOT BE AVAILABLE TO THE CONTRACTOR.

G.N.-406

THE QUANTITIES INCLUDED IN THE PLANS FOR HOT-MIX ASPHALT RESURFACING ARE INTENDED TO GIVE THE COVERAGE SHOWN ON THE TYPICAL CROSS SECTIONS. IT IS NOT INTENDED TO INCREASE THE THICKNESS OF THE HOT-MIX ASPHALT MIXTURE IN ORDER TO USE ALL OF THE QUANTITIES INCLUDED IN THE CONTRACT.

G.N.-406H

MIXTURE REQUIREMENTS

Location(s):	KIRBY AVENUE				
Mixture Use(s):	Surface	Class D Patch			
AC/PG:	PG 64-22	PG 64-22			
RAP %: (Max)**	15%	15%			
Design Air Voids:	4.0% @ Noes=50	4.0% @ N _{cles} =50			
Mixture Composition: (Gradation Mixture)	IL 9.5	IL 9.5			
Friction Aggregate:	Mix D	Mix C			

THE FOLLOWING MIXTURE REQUIREMENTS ARE APPLICABLE FOR THIS PROJECT:

G.N.-1004.01

COARSE AGGREGATE GRADATION CA-10 MAY BE USED WHENEVER COARSE AGGREGATE CA-6 IS SPECIFIED IN THE STANDARD SPECIFICATIONS.

COMMITMENTS

AS A RESULT OF COORDINATION WITH THE CITY OF CHAMPAIGN TO ALLOW THE CLOSURE OF KIRBY AVENUE FOR THESE REPAIRS, THE FOLLOWING SUMMARY OF COMMENTS SERVES AS A COMMITMENT TO THE CITY OF CHAMPAIGN:

- DETOUR SIGNING SHALL BE APPROPRIATELY POSTED
- SPRINGFIELD AVE (IL RTE 10) AND WINDSOR ROAD SHALL REMAIN OPEN FOR THE DURATION OF THE KIRBY AVENUE STRUCTURE REPAIRS
- THE CONTRACTOR SHOULD PLACE PORTABLE MESSAGE BOARDS ON EACH SIDE OF THE BRIDGE AT LEAST 5-DAYS IN ADVANCE OF THE CLOSURE TO ALERT MOTORISTS, PEDESTRIANS, BIKES, AND OTHER USERS OF THE KIRBY AVENUE ROAD CLOSURE.
- CONSTRUCTION SHOULD BE SCHEDULED DURING SUMMER MONTHS ONLY TO AVOID CONFLICTS WITH SCHOOL-YEAR TRAFFIC
- COORDINATE WITH CU-MTD
- MAINTAIN COORDINATION AND COMMUNICATION WITH CITY OF CHAMPAIGN ABOUT THE PROJECT

ci\pu_work\pwidot\bucklesjy\d0265817\057 <mark>0924-sht-Gannote.dgn </mark>	~	
PLOT SCALE = 40.0000 1/10. CHECKED - REVISED -	٠.	
PLOT DATE = 10/5/2011	~	

STATE	OF	ILLINOIS	
DEPARTMENT	0F	TRANSPORTATION	

INDEX OF SHEETS, LIST OF STANDARDS & GENERAL NOTES			F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.		
			Ĺ	57	(10-33HB)BDR	Champaign	27	2	
					CONTRACT	NO. 7	0924		
LE: SHEET NO. OF	SHEETS	STA.	TO STA.			ILLINOIS FED. AIC	PROJECT		