

SUMMARY OF QUANTITIES

LOCATION OF WORK:

FAP 804
U.S. 150
&
Prospect Ave.
95% State
5% City
0021

FAP 804
U.S. 150
&
Prospect Ave.
100% City
0021

CONSTRUCTION TYPE CODE:

URBAN

CODE NO	ITEM	UNIT	TOTAL QUANTITY	0700 QUANTITY	0700 QUANTITY
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	1,070.0	1,070.0	
42400800	DETECTABLE WARNINGS	SQ FT	57.0	57.0	
44000600	SIDEWALK REMOVAL	SQ FT	1,119.0	1,119.0	
67100100	MOBILIZATION	L SUM	1.0	1.0	
70100620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1.0	1.0	
70102622	TRAFFIC CONTROL AND PROTECTION, STANDARD 701502	L SUM	1.0	1.0	
70102632	TRAFFIC CONTROL AND PROTECTION, STANDARD 701602	L SUM	1.0	1.0	
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1.0	1.0	
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1.0	1.0	
81028320	UNDERGROUND CONDUIT, PVC, 1" DIA.	FOOT	164.0	164.0	
81028340	UNDERGROUND CONDUIT, PVC, 1 1/2" DIA.	FOOT	742.0	742.0	
81028350	UNDERGROUND CONDUIT, PVC, 2" DIA.	FOOT	113.0	113.0	
81028360	UNDERGROUND CONDUIT, PVC, 2 1/2" DIA.	FOOT	75.0	75.0	
81028370	UNDERGROUND CONDUIT, PVC, 3" DIA.	FOOT	105.0	105.0	
81028390	UNDERGROUND CONDUIT, PVC, 4" DIA.	FOOT	179.0	179.0	
81028400	UNDERGROUND CONDUIT, PVC, 5" DIA.	FOOT	28.0	28.0	
81400100	HANDHOLE	EACH	11.0	11.0	
81400300	DOUBLE HANDHOLE	EACH	1.0	1.0	
81500130	GULFBOX JUNCTION REMOVAL	EACH	4.0	4.0	
81702110	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO. 10	FOOT	1051.0		1051.0
82102250	LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, 250 WATT	EACH	3.0		3.0
85100500	PAINT NEW TRAFFIC SIGNAL POST	EACH	5.0		5.0

FILE NAME : c:\pwwork\pwwork\biggsrd\0277321\0570	USER NAME : biggsrd 3B-Design.dgn	DESIGNED - _____	REVISED - _____	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SCALE: _____	SHEET _____ OF _____ SHEETS	STA. _____ TO STA. _____	F.A.P. RTE. 804	SECTION 32TS	COUNTY CHAMPAIGN	TOTAL SHEETS 11	SHEET NO. 3
PLOT SCALE : 20,000' / 1" =		CHECKED - _____	REVISED - _____		CONTRACT NO. 70938							
PLOT DATE : 10/31/2011		DATE - _____	REVISED - _____		ILLINOIS FED. AID PROJECT							