

SUMMARY OF QUANTITIES

LOCATION OF WORK: FAI74
 RURAL INTERSTATE
 GPS CORE STATION
 AT SALT KETTLE REST AREA
 VERMILION COUNTY

FUNDING BREAKOUT: 100% STATE
 CONSTRUCTION TYPE CODE: 0044

CODE NO.	ITEM	UNIT	TOTAL QUANTITY
20200100	EARTH EXCAVATION	CU YD	25.0
40200500	AGGREGATE SURFACE COURSE, TYPE A 6"	SQ YD	141.0
66400305	CHAIN LINK FENCE, 6'	FOOT	135.0
66402800	CHAIN LINK GATES, 6' X 5' SINGLE	EACH	1.0
67100100	MOBILIZATION	L SUM	1.0
81028300	UNDERGROUND CONDUIT, PVC, 1/2" DIA.	FOOT	35.0
81028320	UNDERGROUND CONDUIT, PVC, 1" DIA.	FOOT	40.0
81702441	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 2-12/C, 1-12/C GROUND	FOOT	50.0
87800415	CONCRETE FOUNDATION, TYPE E 36-INCH DIAMETER	FOOT	20.0
X0321501	WEED BARRIER FABRIC	SQ YD	141.0
X0325267	GPS ANTENNA PEDESTAL	EACH	1.0
X0326411	EQUIPMENT CABINET AND PEDESTAL MOUNTED BASE	EACH	1.0

* DENOTES SPECIALTY ITEM

FILE NAME =	USER NAME = hogenb_j	DESIGNED - BJH 9/6/2011	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES	F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
et:\pvc\work\pwidot\hogenb_j\0273753-0576	763-shc-S00-1.dgn	DRAWN -	REVISED -			74	GPS CORE STATION 2012-I	VERMILION	8	3	
PLOT SCALE = 100.0000' / 1"	CHECKED -	REVISED -				CONTRACT NO. 70963					
PLOT DATE = 10/5/2011	DATE -	REVISED -				ILLINOIS FED. AID PROJECT					
				SCALE: _____ SHEET NO. 1 OF 1 SHEETS		STA. _____ TO STA. _____					