

80% FED  
20% STATE

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE			SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT		0004 ROADWAY	0011 STRUCTURE No. 009-2511	0011 STRUCTURE No. 009-0512	CODE NO	ITEM	UNIT				
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	1									
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1									
70100500	TRAFFIC CONTROL AND PROTECTION, STANDARD 701326	L SUM	1	1									
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	5	5									
70106500	TEMPORARY BRIDGE TRAFFIC SIGNALS	EACH	1	1									
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	2549	2549									
70300230	TEMPORARY PAVEMENT MARKING - LINE 5"	FOOT	11363	11363									
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	60	60									
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SO FT	3390	3390									
70400100	TEMPORARY CONCRETE BARRIER	FOOT	1200	1200									
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	1175	1175									
70500500	TEMPORARY STEEL PLATE BEAM GUARDRAIL, ATTACHED TO STRUCTURES	FOOT	25		25								
78001120	PAINT PAVEMENT MARKING - LINE 5"	FOOT	11363	11363									
78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	74	74									
78200410	GUARDRAIL MARKERS, TYPE A	EACH	16	16									
78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	4	4									
78300100	PAVEMENT MARKING REMOVAL	SO FT	1825	1825									
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	74	74									
<b>Z0004552</b>	<b>APPROACH SLAB REMOVAL</b>	<b>50 YD</b>	<b>151</b>			<b>151</b>							
Z0007601	BUILDING REMOVAL NO. 1	L SUM	1	1									
Z0007602	BUILDING REMOVAL NO. 2	L SUM	1	1									
Z0007603	BUILDING REMOVAL NO. 3	L SUM	1	1									
Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1									
Z0023602	GRANULAR CULVERT BACKFILL	CU YD	278		278								
<b>Z0001900</b>	<b>ASBESTOS BEARING PAD REMOVAL</b>	<b>EACH</b>	<b>44</b>				<b>44</b>						
Z0030260	IMPACT ATTENUATORS, TEMPORARY (FULLY REDIRECTIVE, NARROW), TEST LEVEL 3	EACH	2	2									
Z0030330	IMPACT ATTENUATORS, RELOCATE (FULLY REDIRECTIVE), TEST LEVEL 3	EACH	2	2									
Z0046304	PIPE UNDERDRAINS FOR STRUCTURES, 4"	FOOT	125				125						
Z0049902	REMOVAL AND DISPOSAL OF NON-FRIABLE ASBESTOS, BUILDING NO. 2	L SUM	1	1									
Z0054517	ROCK FILL FOUNDATION	TON	363		363								
Z0073002	TEMPORARY SOIL RETENTION SYSTEM	SO FT	1,423		223		1,200						
X0504200	CONCRETE HEADWALL	EACH	2	2									
X2070304	POROUS GRANULAR EMBANKMENT, SPECIAL	CU YD	489				489						
X4401198	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SO YD	8678	8678									
* X7200201	WIDTH RESTRICTION SIGNING	L SUM	1	1									
<b>Z0100500</b>	<b>TREE REMOVAL, ACRES</b>	<b>ACRE</b>	<b>5.8</b>	<b>5.8</b>									

\*SPECIALTY ITEM

FILE NAME =	USER NAME = sparksgv	DESIGNED - DRH	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES	F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
c:\pwwork\pwwidot\sparksgv\d0279949\0672855-shr-S00.dgn	DRAWN - DRH	REVISED -	614			144 (B-4); 144 (B-5)	CASS	97	4	
PLOT SCALE = 100.0000' / in.	CHECKED - YAM	REVISED -	CONTRACT NO. 72B55							
PLOT DATE = Aug-31-2011 09:49:30AM	DATE - 8/26/2011	REVISED -	FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT							
				SCALE: N/A	SHEET NO. 2 OF 2 SHEETS					