

ENTRANCE IMPROVEMENT SCHEDULE FOR RURAL / URBAN "PPP" PROJECT

LOCATION	TYPE OF ENTRANCE	EX MATERIAL TYPE DRIVE	EX MATERIAL TYPE APRON	LENGTH (FROM EDGE OF PVT/ BIT SHLD TO LIMITS OF IMPROVEMENT)	WIDTH	SHOULDER WIDTH	DRIVEWAY AREA	MAILBOX TURNOUT AREA	TOTAL AREA	PROPOSED HMA THICKNESS	HOT-MIX ASPHALT SURF. REM. - BUTT JOINT	PCC SURF. REM. - BUTT JOINT	PREP. OF BASE	AGG. SURFACE COURSE, TYPE B	BIT (PC)	AGG (PC)	INCIDENTAL HOT-MIX ASPHALT SURFACING
(LT / RT) STA	(FE/PE/CE/MB) (RURAL/URBAN)	(EARTH/AGG./O&C/BIT./PCC)	(EARTH/AGG./O&C/BIT./P.C.C)	FOOT	FOOT	FT	SQ. FT.	SQ. FT.	SQ. FT.	INCH	SQ. YD.	SQ. YD.	SQ. YD.	TON	TON	TON	TON
RT STA. 352+90	PE / RURAL	AGG	AGG	8	12	4	120	0	120	3.5	0.0			1	0.01	0.03	3.00
RT STA. 354+80	PE / RURAL	AGG	AGG	8	12	4	120	0	120	3.5	0.0			1	0.01	0.03	3.00
RT STA. 357+25	PE / RURAL	AGG	AGG	8	16	4	136	0	136	3.5	0.0			1	0.01	0.03	3.00
RT STA. 358+50	CE / RURAL	AGG	AGG	10	24	4	240	0	240	8	0.0			1	0.01	0.05	12.00
RT STA 359+10	MB / RURAL	BIT	BIT				0	336	336	1.5	37.3			0	0.01	0.07	4.00
LT STA. 359+35	CE / RURAL	AGG	AGG	10	24	4	240	0	240	8	0.0			1	0.01	0.05	12.00
RT STA. 360+40	PE / RURAL	AGG	BIT	8	16	4	136	84	220	1.5	24.4			1	0.01	0.05	3.00
RT STA. 364+00	PE / RURAL	AGG	BIT	8	16	4	136	0	136	1.5	15.1			1	0.01	0.03	2.00
LT STA. 365+70	CE / RURAL	AGG	AGG	10	24	4	240	0	240	8	0.0			1	0.01	0.05	12.00
LT STA. 367+00	CE / RURAL	AGG	BIT	10	24	4	240	0	240	1.5	26.7			1	0.01	0.05	3.00
RT STA. 367+10	PE / RURAL	AGG	AGG	8	14	4	128	0	128	3.5	0.0			1	0.01	0.03	3.00
RT STA. 380+60	PE / RURAL	AGG	AGG	8	18	4	144	84	228	3.5	0.0			1	0.01	0.05	5.00
LT STA. 383+50	PE / RURAL	AGG	BIT	8	20	4	152	100	252	1.5	28.0			1	0.01	0.06	3.00
RT STA. 384+05	PE / RURAL	AGG	BIT	8	12	4	120	84	204	1.5	22.7			1	0.01	0.05	2.00
LT STA. 384+15	PE / RURAL	AGG	BIT	8	14	4	128	84	212	1.5	23.6			1	0.01	0.05	2.00
RT STA. 385+65	MB / RURAL	AGG	AGG				0	336	336	3.5	0.0			0	0.01	0.07	8.00
LT STA. 385+65	PE / RURAL	AGG	AGG	8	12	4	120	84	204	3.5	0.0			1	0.01	0.05	5.00
LT STA. 386+30	PE / RURAL	AGG	AGG	8	12	4	120	0	120	3.5	0.0			1	0.01	0.03	3.00
RT STA. 386+80	MB / RURAL	AGG	AGG				0	336	336	3.5	0.0			0	0.01	0.07	8.00
LT STA. 387+55	PE / RURAL	AGG	AGG	8	12	4	120	0	120	3.5	0.0			1	0.01	0.03	3.00
LT STA. 388+00	PE / RURAL	AGG	BIT	8	12	4	120	168	288	1.5	32.0			1	0.01	0.06	3.00
LT STA. 391+25	PE / RURAL	AGG	BIT	8	12	1.5	211	0	211	1.5	23.5			1	0.01	0.05	2.00
RT STA. 399+70	PE / RURAL	AGG	BIT	8	24	1.5	289	129	418	1.5	46.4			2	0.02	0.09	4.00
RT STA. 400+70	PE / RURAL	AGG	BIT	8	20	1.5	263	155	418	1.5	46.4			1	0.02	0.09	4.00
LT STA. 409+20	PE / RURAL	AGG	AGG	8	24	1	315	0	315	3.5	0.0			2	0.01	0.07	7.00
RT STA. 412+30	CE / RURAL	AGG	AGG	10	24	1	387	0	387	8	0.0			1	0.02	0.09	20.00
LT STA. 438+00	PE / RURAL	AGG	AGG	8	12	1.75	202	0	202	3.5	0.0			1	0.01	0.04	5.00
RT STA. 441+00	MB / RURAL	BIT	BIT				0	336	336	1.5	37.3			0	0.01	0.07	4.00
LT STA. 442+15	PE / RURAL	AGG	BIT	8	12	1.5	211	0	211	1.5	23.5			1	0.01	0.05	2.00
LT STA. 443+30	PE / RURAL	AGG	AGG	8	12	4	120	0	120	3.5	0.0			1	0.01	0.03	3.00
RT STA. 447+80	PE / RURAL	AGG	AGG	8	12	4	120	0	120	3.5	0.0			1	0.01	0.03	3.00
RT STA. 451+55	PE / RURAL	AGG	BIT	8	22	4	160	0	160	1.5	17.8			1	0.01	0.04	2.00
LT STA. 452+70	PE / RURAL	AGG	BIT	8	16	4	136	168	304	1.5	33.8			1	0.01	0.07	3.00
RT STA. 454+55	PE / RURAL	AGG	BIT	8	18	4	144	0	144	1.5	16.0			1	0.01	0.03	2.00

• 104RS2,BR3;105RS7,BR3,4;106RS6

FILE NAME =	USER NAME = sparksgw	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SCHEDULE OF QUANTITIES			F.A.P. RFE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
c:\pwwork\pwwork\sparksgw\10265393\0672E43-sht-schedule.dgn	DRAWN -	REVISED -	321					•	PIKE	69	11	
PLOT SCALE = 106.7353' / in.	CHECKED -	REVISED -	CONTRACT NO. 72E43									
PLOT DATE = Oct-31-2011 03:58:40PM	DATE -	REVISED -	SCALE:		SHEET NO. 6 OF 8 SHEETS	STA.	TO STA.	ILLINOIS FED. AID PROJECT				