

SUMMARY OF QUANTITIES

PAY CODE	ITEM	UNITS	0011	
			80% FED.	20% STATE
			QUANTITY	
5421D024	PIPE CULVERTS, CLASS D, TYPE 1 24" (TEMPORARY)	FOOT	71	
59100100	GEOCOMPOSITE WALL DRAIN	SQ YD	95.6	
60100060	CONCRETE HEADWALLS FOR PIPE DRAINS	EACH	4.0	
60100905	PIPE DRAINS 4"	FOOT	50	
60602800	CONCRETE GUTTER, TYPE B	FOOT	406	
63000001	STEEL PLATE BEAM GUARD RAIL, TYPE A, 6 FOOT POSTS	FOOT	612.5	
63100045	TRAFFIC BARRIER TERMINAL, TYPE 2	EACH	1	
63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	4	
63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	5	
63200310	GUARDRAIL REMOVAL	FOOT	974	
63300725	STEEL PLATE BEAM GUARDRAIL (SHORT RADIUS)	FOOT	62.5	
66600105	FURNISHING AND ERECTING RIGHT-OF-WAY MARKERS	EACH	6	
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	20	
67100100	MOBILIZATION	L SUM	1	
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	
70100500	TRAFFIC CONTROL AND PROTECTION, STANDARD 701326	L SUM	1	
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	2	
70106500	TEMPORARY BRIDGE TRAFFIC SIGNALS	EACH	1	
70106700	TEMPORARY RUMBLE STRIP	EACH	6	
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	1044	
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	1815	
70400100	TEMPORARY CONCRETE BARRIER	FOOT	4306	
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	4306	
78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	10660	
78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	63	
78100105	RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE)	EACH	5	
78200410	GUARDRAIL MARKERS, TYPE A	EACH	20	
78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	5	
78300100	PAVEMENT MARKING REMOVAL	SQ FT	1096	
A2001310	TREE, ACER SACCHARINUM (SILVER MAPLE) 1-1/4" CALIPER, BALLED AND BURLAPPED	EACH	10	
A2002714	TREE, CARYA OVATA (SHAGBARK HICKORY), 1-3/4" CALIPER, BALLED AND BURLAPPED	EACH	5	

SUMMARY OF QUANTITIES

PAY CODE	ITEM	UNITS	0011	
			80% FED.	20% STATE
			QUANTITY	
A2004616	TREE, GLEDITSIA TRIACANTHOS INERMIS (THORNLESS COMMON HONEYLOCUST), 2" CALIPER, BALLED AND BURLAPPED	EACH	5	
A2005114	TREE, JUGLANS NIGRA (BLACK WALNUT), 1-3/4" CALIPER, BALLED & BURLAPPED	EACH	25	
A2006914	TREE, QUERCUS PALUSTRIS (PIN OAK), 1-3/4" CALIPER, BALLED AND BURLAPPED	EACH	10	
A2007114	TREE, QUERCUS RUBRA (RED OAK), 1-3/4" CALIPER, BALLED AND BURLAPPED	EACH	10	
B2001114	TREE, CERCIS CANADENSIS (EASTERN REDBUD), 1-3/4" CALIPER, TREE FORM, BALLED AND BURLAPPED	EACH	15	
B2001366	TREE, CORNUS FLORIDA (FLOWERING DOGWOOD), 6' HEIGHT, CLUMP FORM, BALLED AND BURLAPPED	EACH	6	
B2005614	TREE, PYRUS CALLERYANA BRADFORD (BRAD FORD CALLERY PEAR), 1-3/4" CALIPER, TREE FORM, BALLED AND BURLAPPED	EACH	10	
D2C02936	EVERGREEN, PINUS STROBUS (EASTERN WHITE PINE), 3' HEIGHT, CONTAINER	EACH	20	
Z0030251	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE, NARROW), TEST LEVEL 3	EACH	4	
X2070304	POROUS GRANULAR EMBANKMENT, SPECIAL	CU YD	160.4	
X5020501	UNDERWATER STRUCTURE EXCAVATION PROTECTION - LOCATION 1	EACH	1	
X5020502	UNDERWATER STRUCTURE EXCAVATION PROTECTION - LOCATION 2	EACH	1	
50600530	MECHANICAL SPLICERS	EACH	96	
X7010216	TRAFFIC CONTROL & PROTECTION SPECIAL	L SUM	1	
Z0001900	ASBESTOS BEARING PAD REMOVAL	EACH	140	
Z0030250	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3	EACH	2	
Z0030350	IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 3	EACH	2	
Z0046304	PIPE UNDERDRAINS FOR STRUCTURES 4"	FOOT	121	
Z0073002	TEMPORARY SOIL RETENTION SYSTEM	SQ FT	7917	
Z0076600	TRAINEES	HOUR	500	

SPECIALTY ITEMS
0042

PRINTED DATE: 5/11/2011
FILE NAME: m:\projects\des\pib 149, Item 25 - 47, various design work, order 07\road\drawings\Sheets\04_R16_S00_2.dgn



USER NAME = #USER#
DESIGNED - JEH, ADG
DRAWN - JEH, ADG
CHECKED - DF, PAT
DATE - 05-11-2011

DESIGNED - JEH, ADG
DRAWN - JEH, ADG
CHECKED - DF, PAT
DATE - 05-11-2011

REVISED -
REVISED -
REVISED -
REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF
QUANTITIES

SHEET NO 2 OF 2 SHEETS

F.A.P.
RTE.
91

SECTION
(5BR)B-1

COUNTY
COLES

TOTAL SHEETS
91

SHEET NO
4

CONTRACT NO 74244

ILLINOIS FED. AID PROJECT