

RESURFACING SCHEDULE SECTION (19Z)RS-2

STATION TO STATION	LENGTH FOOT	AVERAGE PAVEMENT WIDTH FOOT	AREA SQ YD	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2" SQ YD	BITUMINOUS MATERIALS (PRIME COAT) GALLON	AGGREGATE (PRIME COAT) TON	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N90 TON	TEMPORARY RAMP SQ YD
2+63.00 TO 3+41.00	78.0	53.0	459.3	459.3	45.9	0.9	38.6	29.4
3+41.00 TO 4+54.00	113.0	59.0	740.8	740.8	74.1	1.5	62.2	0.0
4+54.00 TO 5+54.00	100.0	63.0	700.0	700.0	70.0	1.4	58.8	0.0
5+54.00 TO 9+10.00	356.0	66.0	2610.7	2610.7	261.1	5.2	219.3	0.0
9+10.00 TO 30+03.00	2093.0	55.0	12790.6	12790.6	1279.1	25.6	1074.4	0.0
30+03.00 TO 30+40.50	37.5	55.0	229.2	229.2	22.9	0.5	19.3	30.6
1750+22.50 TO 1750+81.00	58.5	36.0	234.0	234.0	23.4	0.5	19.7	40.0
104+00.00 TO 111+44.87	744.9	45.0	3724.4	3724.4	372.4	7.4	312.8	50.0
Richmond East Leg of Intersection	35.0	57.5	223.6	223.6	22.4	0.4	18.8	31.9
TOTALS	3616.0		21712.0	21712.0	2171.0	43.0	1824.0	182.0

FILE NAME =	USER NAME = swartzw	DESIGNED -	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>RESURFACING SCHEDULE SECTION (19Z)RS-2</b>			F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
ca:\pwork\pwork\swartzw\00240046\077	259-sht-schedule.dgn	DRAWN -	REVISED -		SCALE: NA	SHEET NO. 2 OF 2 SHEETS	STA. TO STA.	325	.	.	24	9
	PLOT SCALE = 50.0000' / 1" =	CHECKED -	REVISED -							CONTRACT NO. 74259		
	PLOT DATE = 10/21/2011	DATE -	REVISED -					ILLINOIS FED. AID PROJECT				