

PAVEMENT MARKING SCHEDULE

LOCATION	RAISED REFLECTIVE PAVEMENT MARKER		URETHANE PAVEMENT MARKING - LINE 4"	URETHANE PAVEMENT MARKING - LINE 6"		URETHANE PAVEMENT MARKING - LINE 8"		URETHANE PAVEMENT MARKING - LINE 12"		GROOVING FOR RECESSED PAVEMENT MARKING, LETTERS, NUMBERS AND SYMBOLS (SQ FT)	GROOVING FOR RECESSED PAVEMENT MARKING 5" (FOOT)	GROOVING FOR RECESSED PAVEMENT MARKING 7" (FOOT)	GROOVING FOR RECESSED PAVEMENT MARKING 9" (FOOT)	GROOVING FOR RECESSED PAVEMENT MARKING 13" (FOOT)		
	ONE-WAY CRYSTAL (EACH)	ONE-WAY AMBER		SOLID YELLOW (FOOT)	SKIP DASH WHITE (FOOT)	SOLID WHITE (FOOT)	SKIP DASH WHITE (FOOT)	SOLID YELLOW (FOOT)	SOLID WHITE (FOOT)						SOLID YELLOW (FOOT)	
I-57/70																
2095+64.00 TO 2286+00.00*	1643		352		28090	18205	36068	4204	1122	346	228	22895	46369	4204	1122	
FAYETTE RAMP A																
5+45.16 TO 16+00.00	10	12		600				383				1655		383		
FAYETTE RAMP B																
13+15.00 TO 26+05.43				567			1290	415				1857		415		
FAYETTE RAMP C																
1+99.92 TO 11+00.00	9	7		240			900	361				1140		361		
FAYETTE RAMP D																
19+27.63 TO 31+84.73							1257	410				1257		410		
BIKE TRAIL																
11+50.00 TO 38+50.00					675							675		0		
KELLER RAMP A																
10+00.00 TO 27+56.47	9	28		1095			1756	362				2851		362		
KELLER RAMP B																
18+48.85 TO 38+95.47				300			2047	1582				2347		1582		
KELLER RAMP C																
10+00.00 TO 23+03.36	11	17		658			1304	436				1962		436		
KELLER RAMP D																
16+03.00 TO 28+47.18				530			1244	534				1774		534		
SUBTOTAL	1682	64	352	3990	675	38943	18205	36068	8687	1122	346	228	38413	46369	8687	1122
TOTAL	1746		352	43608		54273		8687	1468			228	38413	46369	8687	1122

* RAISED REFLECTIVE PAVEMENT MARKERS AND PAVEMENT MARKING GROOVING STOP AT STATION 2255+00.00.

DELINEATOR SCHEDULE

LOCATION	DELINEATORS	REMOVE AND REINSTALL DELINEATORS
STATION TO STATION	(EACH)	(EACH)
I-57/70 WB		
2121+44.00 TO 2268+00.00	LT 24	
I-57/70 EB		
2121+44.00 TO 2266+69.59	RT 27	
FAYETTE RAMP A		
6+08.63 TO 16+50.00	LT/RT 20	
FAYETTE RAMP B		
15+00.00 TO 26+05.43	LT/RT 16	
FAYETTE RAMP C		
4+96.49 TO 11+00.00	LT/RT 4	4
FAYETTE RAMP D		
19+27.63 TO 31+84.73	RT 9	3
KELLER RAMP A		
13+06.86 TO 25+52.68	LT/RT 22	
KELLER RAMP B		
18+48.85 TO 38+95.47	RT 21	
KELLER RAMP C		
10+00.00 TO 23+03.36	LT/RT 23	
KELLER RAMP D		
16+03.00 TO 28+47.18	LT/RT 18	
TOTAL	184	7

TEMPORARY PAVEMENT MARKING SCHEDULE

LOCATION	TEMPORARY PAVEMENT MARKING LETTERS AND SYMBOLS (SQ FT)	TEMPORARY PAVEMENT MARKING - LINE 4"		TEMPORARY PAVEMENT MARKING - LINE 6"		TEMPORARY PAVEMENT MARKING - LINE 8"		TEMPORARY PAVEMENT MARKING - LINE 12"		WORK ZONE PAVEMENT MARKING REMOVAL (SQ FT)
		SOLID YELLOW (FOOT)	SKIP DASH WHITE (FOOT)	SOLID WHITE (FOOT)	SOLID WHITE (FOOT)	SOLID YELLOW (FOOT)	SOLID WHITE (FOOT)	SOLID WHITE (FOOT)	SOLID YELLOW (FOOT)	
I-57/70										
2095+64.00 TO 2286+00.00	352			28090	18205	36068	4204	1122	346	41121
FAYETTE RAMP A										
5+45.18 TO 16+00.00		600		1055			383			807
FAYETTE RAMP B										
13+15.00 TO 26+05.43		567		1290			415			896
FAYETTE RAMP C										
1+99.92 TO 11+00.00		240		900			361			620
FAYETTE RAMP D										
19+27.63 TO 31+84.73				1257			410			693
BIKE TRAIL										
11+50.00 TO 38+50.00			675							225
KELLER RAMP A										
10+00.00 TO 27+56.47		1095		1756			362			1192
KELLER RAMP B										
18+48.85 TO 38+95.47		300		2047			1582			1837
KELLER RAMP C										
10+00.00 TO 23+03.36		658		1304			436			944
KELLER RAMP D										
16+03.00 TO 28+47.18		530		1244			534			948
SUBTOTAL	352	3990	675	38943	18205	36068	8687	1122	346	49283
TOTAL	352	43608		54273		8687	1468			49283

TRAFFIC CONTROL SCHEDULE

LOCATION	TEMPORARY CONCRETE BARRIER (FOOT)	RELOCATE TEMPORARY CONCRETE BARRIER (FOOT)	TCB* TO REMAIN IN PLACE (FOOT)	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3 (EACH)	IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 3 (EACH)
STATION TO STATION	ROADWAY				
STAGE 1					
2118+73 TO 2268+00	I-57/70 EB	14662.5		1	
2121+44 TO 2270+61	I-57/70 WB	14737.5		1	
2145+41 TO 2147+18	I-57/70 EB	175.0		1	
2145+65 TO 2147+42	I-57/70 WB	175.0		1	
PRE-STAGE 2A					
2118+79 TO 2268+00	I-57/70 EB	14662.5			1
2121+44 TO 2270+68	I-57/70 WB	14737.5			1
2145+41 TO 2147+18	I-57/70 EB		175.0		
2145+65 TO 2147+42	I-57/70 WB		175.0		
PRE-STAGE 2B					
2118+79 TO 2268+00	I-57/70 EB		14662.5		
2121+44 TO 2270+68	I-57/70 WB		14737.5		
2145+41 TO 2147+18	I-57/70 EB		175.0		
2145+65 TO 2147+42	I-57/70 WB		175.0		
STAGE 2					
2116+52 TO 2121+19	I-57/70 EB	437.5			1
2121+19 TO 2136+00	I-57/70 EB		1462.5		
2137+98 TO 2151+17	I-57/70 EB		1275.0		1
2154+05 TO 2186+85	I-57/70 EB	50.0	3187.5	1	
2188+65 TO 2209+92	I-57/70 EB		2062.5	1	
2195+85 TO 2209+93	I-57/70/KEL RAMP E	1350.0		1	
2214+21 TO 2268+00	I-57/70 EB		5262.5	1	
2121+44 TO 2135+76	I-57/70 WB	50.0	1337.5		1
2138+65 TO 2155+51	I-57/70 WB		1637.5	1	
2157+45 TO 2190+44	I-57/70 WB	50.0	3187.5	1	
2193+30 TO 2213+87	I-57/70 WB	25.0	1987.5	1	
2215+87 TO 2268+00	I-57/70 WB		5162.5		
2268+00 TO 2270+67	I-57/70 WB	237.5			1
PAY TOTAL	29750.0	31600.0		11	6

* FOR INFORMATION ONLY