


KELLER RAMP C						
POINT	ELEVATION	NORTHING	EASTING	ROADWAY STATION	ROADWAY OFFSET	RAMP STATION
EB FAI ROUTE 57/70						
715	576.09	897,209.37	918,487.69	2183+25.00	81.30	13+54.08
716	576.26	897,232.25	918,497.16	2183+50.00	82.95	13+78.83
717	576.44	897,255.11	918,506.62	2183+75.00	84.51	14+03.58
718	576.62	897,277.96	918,516.08	2184+00.00	85.98	14+28.31
719	576.80	897,300.81	918,525.53	2184+25.00	87.35	14+53.04
KELLER RAMP C						
720	576.92	897,321.10	918,533.93			14+75.00
721	577.07	897,344.20	918,543.49			15+00.00
722	577.20	897,367.30	918,553.05			15+25.00
723	577.33	897,390.40	918,562.61			15+50.00
724	577.47	897,413.50	918,572.17			15+75.00
725	577.60	897,436.60	918,581.73			16+00.00
726	577.73	897,459.60	918,591.54			16+25.00
727	577.87	897,482.26	918,602.09			16+50.00
728	578.00	897,504.57	918,613.37			16+75.00
729	578.19	897,526.49	918,625.38			17+00.00
730	578.39	897,548.01	918,638.11			17+25.00

KELLER RAMP D						
POINT	ELEVATION	NORTHING	EASTING	ROADWAY STATION	ROADWAY OFFSET	RAMP STATION
WB FAI ROUTE 57/70						
800	580.84	897,420.89	918,405.64	2184+97.77	66.00	28+47.18
801	580.85	897,423.03	918,406.37	2185+00.00	66.05	28+44.92
802	581.02	897,446.92	918,414.53	2185+25.00	66.60	28+19.68
803	581.18	897,470.82	918,422.68	2185+50.00	67.26	27+94.42
804	581.34	897,494.72	918,430.85	2185+75.00	68.00	27+69.17
805	581.49	897,518.63	918,439.01	2186+00.00	68.83	27+43.90
806	581.63	897,542.54	918,447.17	2186+25.00	69.76	27+18.64
807	581.81	897,566.46	918,455.34	2186+50.00	70.78	26+93.36
808	582.00	897,590.39	918,463.51	2186+75.00	71.89	26+68.08
809	582.20	897,614.27	918,471.82	2187+00.00	72.94	26+42.79
810	582.39	897,638.01	918,480.49	2187+25.00	73.71	26+17.51
811	582.58	897,661.62	918,489.52	2187+50.00	74.18	25+92.24
812	582.78	897,685.08	918,498.90	2187+75.00	74.36	25+66.97
813	582.97	897,708.40	918,508.64	2188+00.00	74.25	25+41.70
814	583.16	897,731.65	918,518.55	2188+25.00	74.04	25+16.43
815	583.35	897,754.89	918,528.46	2188+50.00	73.92	24+91.16
816	583.55	897,778.13	918,538.38	2188+75.00	73.89	24+65.89
817	583.74	897,801.38	918,548.29	2189+00.00	73.96	24+40.62



FILE NAME =  
S:\projects\107-0000\21-70.dwg V.L. Jullie\pwr.dwg

USER NAME = bseibe1  
PLOT SCALE = 40.0000' / IN.  
PLOT DATE = 3/17/2011

DESIGNED - ESW  
DRAWN - PDB  
CHECKED - BRM  
DATE - 4-23-08

REVISED -  
REVISED -  
REVISED -  
REVISED -

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

**PAVEMENT ELEVATION DETAIL, RAMP D AND C, KELLER AVE.**

SCALE: 1"=20'    SHEET NO. 2 OF 7 SHEETS    STA. 2183+00.00 TO STA. 2189+00.00

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
57/70	(25-3,4)R	EFFINGHAM	1098	220
CONTRACT NO. 74299				
FED. ROAD DIST. NO.	ILLINOIS FED. AID PROJECT			