

GENERAL NOTES

SHORT-TERM PAVEMENT MARKING SHALL BE APPLIED AS FOLLOWS:
TEMPORARY TAPE SHALL BE USED ON THE SURFACE COURSE AND PAINT SHALL BE USED ON THE MILLED SURFACE.

THE HMA SURFACE REMOVAL AND RESURFACING SHALL BE DONE IN A MANNER THAT DOES NOT RESULT IN A GREATER ELEVATION DIFFERENTIAL BETWEEN OPEN LANES THAN ALLOWED BY ARTICLE 701.07 OF THE STANDARD SPECIFICATIONS.

THE TOTAL QUANTITY OF PAINT PAVEMENT MARKING - LINE 4" CONSISTS OF 25,991 FEET OF YELLOW AND 47,481 FEET OF WHITE.

ALL RAISED REFLECTIVE PAVEMENT MARKERS SHALL BE TWO-WAY AMBER MARKERS.

THE ACTUAL LOCATIONS OF PAVEMENT PATCHES SHALL BE DETERMINED BY THE RESIDENT ENGINEER.

THE CONTRACTOR SHALL PROVIDE INTERNET ACCESS TO THE HOT-MIX ASPHALT PLANT QUALITY CONTROL LAB SO THAT HOT-MIX ASPHALT PLANT REPORTS CAN BE E-MAILED TO THE DISTRICT HEADQUARTERS. THIS WORK SHALL BE INCLUDED IN THE COST OF ALL HOT-MIX ASPHALT ITEMS.

THE CONTRACTOR SHALL USE EITHER RC-70 OR AN EMULSIFIED POLYMER PRIME SS-1HP OR SS-1H FOR THE PAY ITEM BITUMINOUS MATERIALS (PRIME COAT).

AGGREGATE FOR AGGREGATE SHOULDERS SHALL BE CRUSHED STONE, CRUSHED CONCRETE OR RAP. AGGREGATE FOR AGGREGATE SURFACE COURSE, TYPE B, SHALL BE CRUSHED STONE OR CRUSHED CONCRETE. RAP SHALL NOT BE USED AS AGGREGATE SHOULDERS, TYPE B WITHIN THE VILLAGE LIMITS OF BLUFF CITY.

THE PAY ITEM TEMPORARY RAMP HAS BEEN INCLUDED FOR THE CONSTRUCTION OF TEMPORARY RAMPS IN ACCORDANCE WITH ARTICLE 406.08 OF THE STANDARD SPECIFICATIONS. THE CONTRACT UNIT PRICE PER SQUARE YARD FOR TEMPORARY RAMP SHALL INCLUDE BOTH THE INSTALLATION AND THE REMOVAL OF THE RAMPS.

THE FOLLOWING MIXTURE REQUIREMENTS ARE APPLICABLE TO THIS PROJECT:

APPLICATION	AC/PG	DESIGN AIR VOIDS	MIXTURE COMPOSITION	FRICTION AGGREGATE
SURFACE COURSE	PG 64-22	4.0% @ N=70	IL - 9.5	MIXTURE C
LEVELING BINDER	PG 64-22	4.0% @ N=70	IL - 9.5	N/A
INCIDENTAL SURFACE	PG 64-22	4.0% @ N=70	IL - 9.5	MIXTURE C
CLASS D PATCHING	PG 64-22	4.0% @ N=70	IL - 19.0	N/A

INDEX OF SHEETS

SHEET NO.	TITLE
1	COVER SHEET
2	GENERAL NOTES, INDEX OF SHEETS, LIST OF STANDARDS
3	SUMMARY OF QUANTITIES
4	LOCATION MAP
5	TYPICAL SECTIONS
6-7	SCHEDULE OF QUANTITIES
8	PAVING DETAILS
9	ENTRANCE SCHEDULE
10-13	STRIPING SHEETS

THE FOLLOWING STANDARDS ARE A PART OF THESE PLANS AND ARE INCLUDED FOLLOWING THE LAST NUMBERED SHEET OF THE PLANS.

STD. NO.	DESCRIPTION
000001-06	STANDARD SYMBOLS, ABBREVIATIONS AND PATTERNS
001006	DECIMAL OF AN INCH AND OF A FOOT
442201-03	CLASS C AND D PATCHES
667101-02	PERMANENT SURVEY MARKERS
701006-03	OFF-RD OPERATIONS, 2L, 2W, 15' TO 24" FROM PAVEMENT EDGE
701011-02	OFF-RD MOVING OPERATIONS, 2L, 2W, DAY ONLY
701201-04	LANE CLOSURE, 2L, 2W, DAY ONLY, FOR SPEEDS >= 45 MPH
701301-04	LANE CLOSURE, 2L, 2W, SHORT TIME OPERATIONS
701306-03	LANE CLOSURE, 2L, 2W, SLOW MOVING OPERATIONS DAY ONLY, FOR SPEEDS >= 45 MPH
701311-03	LANE CLOSURE, 2L, 2W MOVING OPERATIONS-DAY ONLY
701456-02	PARTIAL EXIT RAMP CLOSURE FREEWAY/EXPRESSWAY
701901-02	TRAFFIC CONTROL DEVICES
780001-03	TYPICAL PAVEMENT MARKINGS
781001-03	TYPICAL APPLICATIONS RAISED REFLECTIVE PAVEMENT MARKERS

FILE NAME =	USER NAME = administrator	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	GENERAL NOTES AND INDEX OF SHEETS	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
c:\pwork\pwork\swartzr\08148615\077415\sh: index.dgn	DRAWN -	REVISED -	752			(23-2)RS-1,(W,V)RS-2	FAYETTE	13	2	
PLOT SCALE = 100.0000' / 1"	CHECKED -	REVISED -	CONTRACT NO. 74415							
PLOT DATE = 10/27/2011	DATE -	REVISED -	ILLINOIS FED. AID PROJECT							
				SCALE: NA	SHEET 1 OF 1 SHEETS	STA.	TO STA.			