

PERMANENT SURVEY MARKERS, TYPE I

LOCATION	DESCRIPTION	EACH
P. T. 52+67.89	MAG NAIL W/ WASHER	1
P. C. 56+11.12	MAG NAIL W/ ALUM. TAG	1
P. T. 63+48.97 = 31+23.58	MAG NAIL W/ ALUM. TAG	1
P. O. T. 32+00.00	MAG NAIL W/ WASHER	1
P. I. 43+99.97	MAG NAIL W/ ALUM. TAG	1
P. O. T. 64+95.03	MAG NAIL W/ ALUM. TAG	1
P. O. T. 73+95.69	MAG NAIL W/ ALUM. TAG	1
P. O. T. 80+00.00	MAG NAIL W/ ALUM. TAG	1
P. O. T. 87+00.00	MAG NAIL W/ ALUM. TAG	1
P. O. T. 100+70.88	MAG NAIL W/ ALUM. TAG	1
P. C. 104+28.81	MAG NAIL W/ ALUM. TAG	1
P. O. T. 76+68.27	MAG NAIL	1
P. T. 117+85.00	MAG NAIL	1
P. T. 121+23.45	MAG NAIL W/ WASHER	1
P. C. 122+33.42	MAG NAIL	1
P. T. 143+61.34	MAG NAIL	1
TOTAL =		16

STRIPING SCHEDULE			PAINT PAVEMENT MARKING - LINE 4"	SHORT TERM PAVEMENT MARKING	WORK ZONE PAVEMENT MARKING REMOVAL	RAISED REFLECTIVE PAVEMENT MARKER
STATION TO STATION						
49+82	TO	65+49	3361	470	52	20
65+48.71 TO 33+55.00			STATION EQUATION			
33+55	TO	174+15	29397	4218	469	176
174+15.40 TO 0+00.00			STATION EQUATION			
0+00	TO	33+77	7111	1013	113	42
33+77.00 TO 102+92.10			STATION EQUATION			
102+92	TO	119+32	3071	492	55	21
119+32.10 TO 119+34.57			STATION EQUATION			
119+35	TO	120+94	319	48	5	2
120+94.05 TO 119+99.41			STATION EQUATION			
119+99	TO	162+95	8591	1289	143	54
NO PASSING ZONES						
EASTBOUND:						
98+85	TO	110+12	1127	-	-	-
132+93	TO	138+16	523	-	-	-
160+68	TO	174+15	1347	-	-	-
174+15.40 TO 0+00.00			STATION EQUATION			
0+00	TO	7+05	705	-	-	-
19+12	TO	33+77	1465	-	-	-
33+77.00 TO 102+92.10			STATION EQUATION			
102+92	TO	119+32	1640	-	-	-
119+32.10 TO 119+34.57			STATION EQUATION			
119+35	TO	120+94	159	-	-	-
120+94.05 TO 119+99.41			STATION EQUATION			
119+99	TO	162+95	4296	-	-	-
WESTBOUND:						
49+82	TO	55+09	527	-	-	-
109+05	TO	116+48	743	-	-	-
140+60	TO	145+81	521	-	-	-
170+40	TO	174+15	375	-	-	-
174+15.40 TO 0+00.00			STATION EQUATION			
0+00	TO	17+55	1755	-	-	-
30+32	TO	33+77	345	-	-	-
33+77.00 TO 102+92.10			STATION EQUATION			
102+92	TO	119+32	1640	-	-	-
119+32.10 TO 119+34.57			STATION EQUATION			
119+35	TO	120+94	159	-	-	-
120+94.05 TO 119+99.41			STATION EQUATION			
119+99	TO	162+95	4296	-	-	-
TOTALS:			73472	7530	837	314

FILE NAME =	USER NAME = administrator	DESIGNED -	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>SCHEDULE OF QUANTITIES</b>		F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
c:\pwork\pwork\swartzw\d0148615\077415-ahtrschdgn		DRAWN -	REVISED -		SCALE: NA	SHEET 2 OF 2 SHEETS	STA.	TO STA.	752	(23-2)RS-1, (W,V)RS-2	FAYETTE	13 7
PLOT SCALE = 50,0000' / 1"		CHECKED -	REVISED -		CONTRACT NO. 74415							
PLOT DATE = 10/27/2011		DATE -	REVISED -		ILLINOIS FED. AID PROJECT							