

SUMMARY OF QUANTITIES

SUMMARY OF QUANTITIES			URBAN TOTAL QUANTITIES	CONSTRUCTION TYPE CODE			SUMMARY OF QUANTITIES			URBAN TOTAL QUANTITIES	CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT		90% FEDERAL 10% STATE 0005	0014	100% STATE 0005	CODE NO	ITEM	UNIT		90% FEDERAL 10% STATE 0005	0014	100% STATE 0005
X63000017	STEEL PLATE BEAM GUARDRAIL, TYPE D, 6 FOOT POSTS	FOOT	487.5	487.5		70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	154206	63590	90616		
X63100045	TRAFFIC BARRIER TERMINAL, TYPE 2	EACH	9	9		70300250	TEMPORARY PAVEMENT MARKING - LINE 8"	FOOT	23370	19370	4000		
X63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	9	9		70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	48		48		
X63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	7	7		70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	23936	2162	21774		
X63100169	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) FLARED	EACH	5	5		70400100	TEMPORARY CONCRETE BARRIER	FOOT	5255		5255		
63200310	GUARDRAIL REMOVAL	FOOT	4928	4928		70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	2575		2575		
63500105	DELINEATORS	EACH	248	248		X72000300	SIGN PANEL - TYPE 3	SQ FT	2836		2836		
63700175	CONCRETE BARRIER, SINGLE FACE, 42 INCH HEIGHT	FOOT	688	688		72400330	REMOVE SIGN PANEL - TYPE 3	SQ FT	3162	3162			
63700255	CONCRETE BARRIER, DOUBLE FACE, 32 INCH HEIGHT	FOOT	250	250		X73301810	OVERHEAD SIGN STRUCTURE WALKWAY, TYPE A	FOOT	36	36			
63700275	CONCRETE BARRIER, DOUBLE FACE, 42 INCH HEIGHT	FOOT	2882	2882		73602000	REMOVE OVERHEAD SIGN STRUCTURE - BRIDGE MOUNTED	EACH	1		1		
63700805	CONCRETE BARRIER TRANSITION	FOOT	10	10		73801100	REMOVE AND REERECT OVERHEAD SIGN STRUCTURE-SPAN	EACH	1	1			
64200116	SHOULDER RUMBLE STRIPS, 16 INCH	FOOT	51157	51157		X78003110	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LINE 4"	FOOT	2096	2096			
64300260	IMPACT ATTENUATORS (FULLY REDIRECTIVE, NARROW), TEST LEVEL 3	EACH	2	2		X78003140	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - LINE 8"	FOOT	580	580			
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	11	11		X78004210	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - INLAID - LINE 4"	FOOT	61494	61494			
67100100	MOBILIZATION	L SUM	1	1		X78004240	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - INLAID - LINE 8"	FOOT	18790	18790			
70100201	TRAFFIC CONTROL AND PROTECTION, STANDARD 701402	EACH	0	0		X78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	1426	1426			
70100405	TRAFFIC CONTROL AND PROTECTION, STANDARD 701321	EACH	2	1	1	X78100105	RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE)	EACH	63	63			
70100420	TRAFFIC CONTROL AND PROTECTION, STANDARD 701411	EACH	1	1		78200410	GUARDRAIL MARKERS, TYPE A	EACH	66	66			
70100500	TRAFFIC CONTROL AND PROTECTION, STANDARD 701326	L SUM	1		1	78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	12	12			
70100700	TRAFFIC CONTROL AND PROTECTION, STANDARD 701406	L SUM	1	1		78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	1488	1488			
70100800	TRAFFIC CONTROL AND PROTECTION, STANDARD 701401	L SUM	1	1		80300100	LOCATING UNDERGROUND CABLE	FOOT	70	70			
70100815	TRAFFIC CONTROL AND PROTECTION, STANDARD 701446	L SUM	1	1		81028200	UNDERGROUND CONDUIT, GALVANIZED STEEL, 2" DIA.	FOOT	280	280			
70100825	TRAFFIC CONTROL AND PROTECTION, STANDRAD 701456	L SUM	1	1		81028220	UNDERGROUND CONDUIT, GALVANIZED STEEL, 3" DIA.	FOOT	130	130			
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	130	130		81200230	CONDUIT EMBEDDED IN STRUCTURE, 2" DIA., PVC	FOOT	2306	2,306			
70106500	TEMPORARY BRIDGE TRAFFIC SIGNALS	EACH	1		1	81200250	CONDUIT EMBEDDED IN STRUCTURE, 3" DIA., PVC	FOOT	10	10			
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	60	60		X81300986	JUNCTION BOX, STAINLESS STEEL, EMBEDDED IN STRUCTURE, 8" X 24" X 10"	EACH	4	4			
70200100	NIGHTTIME WORK ZONE LIGHTING	L SUM	1	1		X81702410	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 3-1/C NO. 4	FOOT	960	960			
70300100	SHORT TERM PAVEMENT MARKING	FOOT	29461	19461	10000	X81702415	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 3-1/C NO. 6	FOOT	1432	1432			

*SPECIALTY ITEM

FILE NAME =	USER NAME = burnsideem	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES	F.A.I. RTE. 64	SECTION 82-(3,4)RS	COUNTY ST. CLAIR	TOTAL SHEETS 167	SHEET NO. 6
CONTRACT NO. 76415										