

CONCRETE BARRIER										
LOCATION				CONCRETE BARRIER DOUBLE FACE, 42" HEIGHT	CONCRETE BARRIER SINGLE FACE, 42" HEIGHT	CONCRETE BARRIER DOUBLE FACE, 32" HEIGHT	CONCRETE BARRIER TRANSITION	PROTECTIVE COAT	POROUS GRANDULAR EMBANKMENT	CONCRETE MEDIAN SURFACE 4"
STA	TO	STA	RT/LT	(FOOT)	(FOOT)	(FOOT)	(FOOT)	(SQ YD)	(CU YD)	(SQ FT)
I-64 EASTBOUND										
259+23.83	TO	261+46.00	RT	222				173		
261+46.00	TO	263+26.00	RT		360			280	70	180
263+26.00	TO	276+94.75	RT	1369				1065		
284+92.00	TO	285+02.00	RT			10		6		
285+98.00	TO	286+08.00	RT			10		6		
287+04.00	TO	287+14.00	RT			10		6		
287+92.00	TO	288+02.00	RT			10		6		
288+95.00	TO	289+05.00	RT			10		6		
289+95.00	TO	290+05.00	RT			10		6		
290+95.00	TO	291+05.00	RT			10		6		
291+95.00	TO	292+05.00	RT			10		6		
292+95.00	TO	293+05.00	RT			10		6		
293+95.00	TO	294+05.00	RT			10		6		
294+95.00	TO	295+05.00	RT			10		6		
295+95.00	TO	296+05.00	RT			10		6		
I-64 WESTBOUND										
266+05.95	TO	278+97.25	LT	1291				1004		
278+97.25	TO	279+07.25	LT				10	10		
279+07.25	TO	280+71.00	LT		328			260	193	495
286+95.00	TO	287+05.00	LT			10		6		
288+22.00	TO	288+32.00	LT			10		6		
289+45.00	TO	289+55.00	LT			10		6		
290+70.00	TO	290+80.00	LT			10		6		
291+95.00	TO	292+05.00	LT			10		6		
293+23.00	TO	293+33.00	LT			10		6		
294+45.00	TO	294+55.00	LT			10		6		
295+70.00	TO	295+80.00	LT			10		6		
296+95.00	TO	297+05.00	LT			10		6		
298+20.00	TO	298+30.00	LT			10		6		
299+45.00	TO	299+55.00	LT			10		6		
900+70.00	TO	900+80.00	LT			10		6		
301+95.00	TO	302+05.00	LT			10		6		
TOTAL:				2882	688	250	10	2940	263	675

NOTE: EASTBOUND STA. 276+84.75 TO STA. 276+94.75 AND WESTBOUND STA. 280+61 TO STA. 280+71 WILL TRANSITION FROM 42" HEIGHT TO THE EXISTING 32" HEIGHT CONCRETE BARRIER

CONCRETE BARRIER REMOVAL					
LOCATION			CONCRETE BARRIER REMOVAL	CONCRET MEDIAN SURFACE REMOVAL	CONCRETE REMOVAL
STA	TO	STA	(FOOT)	(SQ FT)	(CU YD)
I-64 EASTBOUND - RT					
259+23.83	TO	261+46.00	222		
261+46.00	TO	262+30.50	169	90	
262+30.50	TO	262+44.00			2
262+44.00	TO	263+26.00	164	90	
263+26.00	TO	276+94.75	1369		
284+92.00	TO	285+02.00	10		
285+98.00	TO	286+08.00	10		
287+04.00	TO	287+14.00	10		
287+92.00	TO	288+02.00	10		
288+95.00	TO	289+05.00	10		
289+95.00	TO	290+05.00	10		
290+95.00	TO	291+05.00	10		
291+95.00	TO	292+05.00	10		
292+95.00	TO	293+05.00	10		
293+95.00	TO	294+05.00	10		
294+95.00	TO	295+05.00	10		
295+95.00	TO	296+05.00	10		
I-64 WESTBOUND - LT					
266+05.95	TO	278+97.25	1291		
278+97.25	TO	279+07.25	10	41	
279+07.25	TO	280+71.00	328	670	
286+95.00	TO	287+05.00	10		
288+22.00	TO	288+32.00	10		
289+45.00	TO	289+55.00	10		
290+70.00	TO	290+80.00	10		
291+95.00	TO	292+05.00	10		
293+23.00	TO	293+33.00	10		
294+45.00	TO	294+55.00	10		
295+70.00	TO	295+80.00	10		
296+95.00	TO	297+05.00	10		
298+20.00	TO	298+30.00	10		
299+45.00	TO	299+55.00	10		
300+70.00	TO	300+80.00	10		
301+95.00	TO	302+05.00	10		
TOTAL:			3803	891	2