

80% FEDERAL
20% STATE
LICE L

SUMMARY OF QUANTITIES												
ITEM #	ITEM DESCRIPTION	UNIT	URBAN TOTAL QUANTITY	0004	0005	01	02	03	04	01	02	03
				ROADWAY	RESURFACING	BRIDGE SN 082-0117	BRIDGE SN 082-0118	BRIDGE SN 082-0119	BRIDGE SN 082-0120	MSE RET WALL SN 082-W311	MSE RET WALL SN 082-W312	MSE RET WALL SN 082-W313
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	2,265	2,265								
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	416	416								
20101100	TREE TRUNK PROTECTION	EACH	24	24								
20200100	EARTH EXCAVATION	CU YD	3,785	3,318	467							
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	4,208	4,208								
20400100	BORROW EXCAVATION	CU YD	78,680	76,712	1,968							
20800150	TRENCH BACKFILL	CU YD	872	872								
* 25000200	SEEDING, CLASS 2	ACRE	2.75	2.75								
* 25000210	SEEDING, CLASS 2A	ACRE	5.00	5.00								
* 25000400	NITROGEN FERTILIZER NUTRIENT	POUND	698	698								
* 25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	698	698								
* 25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	698	698								
* 25100115	MULCH, METHOD 2	ACRE	30.25	30.25								
25100635	HEAVY DUTY EROSION CONTROL BLANKET	SQ YD	15,261	15,023	238							
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	2,250	2,250								
28000305	TEMPORARY DITCH CHECKS	FOOT	340	340								
28000400	PERIMETER EROSION BARRIER	FOOT	8,170	8,170								
28000500	INLET AND PIPE PROTECTION	EACH	23	23								
28100105	STONE RIPRAP, CLASS A3	SQ YD	638	638								
31101100	SUBBASE GRANULAR MATERIAL, TYPE B	CU YD	2,951	2,951								
31102000	SUBBASE GRANULAR MATERIAL, TYPE C	CU YD	670			110	120	230	210			
31200110	STABILIZED SUBBASE 6"	SQ YD	5,103	5,103								
35100100	AGGREGATE BASE COURSE, TYPE A	TON	2,082	1,067	1,015							
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	666	375	291							
40600300	AGGREGATE (PRIME COAT)	TON	13.4	4.6	8.8							
40600827	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	386	260	126							
40600895	CONSTRUCTING TEST STRIP	EACH	2	2								
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	297	244	53							
40603335	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50	TON	163	163								
40603092	HOT-MIX ASPHALT BINDER COURSE, IL -19.0, FG, N90	TON	1,403		1,403							
40603545	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N90	TON	749	259	490							
40701881	HOT-MIX ASPHALT PAVEMENT (FULL-DEPTH), 10"	SQ YD	8,852	8,852								
42000500	PORTLAND CEMENT CONCRETE PAVEMENT 10"	SQ YD	3,095	3,095								
42001300	PROTECTIVE COAT	SQ YD	6,549	6,549								
42001420	BRIDGE APPROACH PAVEMENT CONNECTOR (PCC)	SQ YD	1,616	1,616								

* DENOTES SPECIALTY ITEM

FILE NAME = 0876884-sh1-summary.dgn	USER NAME = thomps-d	DESIGNED GC	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES			F.A.P. RTE	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
MODEL NAME = #MODELNAME#	DRAWN RDT	REVISED -	103					27-1-VHB-1	ST. CLAIR	277	3	
PLOT SCALE = 20,000 / IN.	CHECKED JAP	REVISED -	SCALE: NONE SHEET NO. 1 OF 5 SHEETS STA. ----- TO STA. -----			CONTRACT NO. 76884						
PLOT DATE = 10/20/2011	DATE 10-19-11	REVISED -	ILLINOIS FED. AID PROJECT									