

80% FEDERAL  
20% STATE  
LICE L

SUMMARY OF QUANTITIES												
ITEM #	ITEM DESCRIPTION	UNIT	URBAN TOTAL QUANTITY	0004	0005	0011	0011	0011	0011	0040	0040	0040
				ROADWAY	RESURFACING	BRIDGE SN 082-0117	BRIDGE SN 082-0118	BRIDGE SN 082-0119	BRIDGE SN 082-0120	MSE RET WALL SN 082-W311	MSE RET WALL SN 082-W312	MSE RET WALL SN 082-W313
42001500	P. C. CONCRETE BRIDGE APPROACH SHOULDER PAVEMENT	SQ YD	1,516	1,516								
44000100	PAVEMENT REMOVAL	SQ YD	12,583	12,583								
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SQ YD	5,828		5,828							
44004250	PAVED SHOULDER REMOVAL	SQ YD	7,711	4,588	3,123							
48100500	AGGREGATE SHOULDERS, TYPE A 6"	SQ YD	127		127							
48203029	HOT-MIX ASPHALT SHOULDERS, 8"	SQ YD	9,787	6,148	3,639							
50100300	REMOVAL OF EXISTING STRUCTURES NO. 1	EACH	1			1						
50100400	REMOVAL OF EXISTING STRUCTURES NO. 2	EACH	1				1					
50157300	PROTECTIVE SHIELD	SQ YD	1,279			296	296	344	343			
50200100	STRUCTURE EXCAVATION	CU YD	4,129			253	253			2068	635	920
50300225	CONCRETE STRUCTURES	CU YD	1,899.4			442	439	109.3	109.1			
50300255	CONCRETE SUPERSTRUCTURE	CU YD	1,885.2			549.5	549.5	393.1	393.1			
50300260	BRIDGE DECK GROOVING	SQ YD	4,042			1480	1480	541	541			
50300300	PROTECTIVE COAT	SQ YD	5,055			1,848	1,847	680	680			
50400105	PRECAST CONCRETE BRIDGE SLAB	SQ FT	5,020			2,510	2,510					
50400745	FURNISHING AND ERECTING PRECAST PRESTRESSED CONCRETE BULB T-BEAMS 72"	FOOT	2,021.50					1,010.75	1,010.75			
50500105	FURNISHING AND ERECTING STRUCTURAL STEEL	L SUM	1			0.5	0.5					
50500505	STUD SHEAR CONNECTORS	EACH	10,440			5,220	5,220					
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	629,420			227,450	227,850	87,180	86,940			
50800515	BAR SPLICERS	EACH	180					90	90			
50800530	MECHANICAL SPLICERS	EACH	512			256	256					
51100100	SLOPE WALL 4 INCH	SQ YD	373			16	16	188	153			
51201600	FURNISHING STEEL PILES HP12X53	FOOT	10,378			3,677	3,689	1,488	1,524			
51202305	DRIVING PILES	FOOT	10,378			3,677	3,689	1,488	1,524			
51203600	TEST PILE STEEL HP12X53	EACH	10			3	3	2	2			
51204650	PILE SHOES	EACH	184			66	66	26	26			
51500100	NAME PLATES	EACH	7			1	1	1	1			
52100010	ELASTOMERIC BEARING ASSEMBLY, TYPE I	EACH	26			5	5	8	8			
52100020	ELASTOMERIC BEARING ASSEMBLY, TYPE II	EACH	10			5	5					
52100520	ANCHOR BOLTS, 1"	EACH	52			10	10	16	16			
52100540	ANCHOR BOLTS, 1 1/2"	EACH	40			20	20					
54001061	GRATED BOX CULVERT END SECTIONS, CULVERT NO. 01	EACH	2	2								
54010603	PRECAST CONCRETE BOX CULVERTS 6' X 3'	FOOT	452	452								
54213657	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 12"	EACH	8	8								
54213660	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 15"	EACH	1	1								

\* DENOTES SPECIALTY ITEM

FILE NAME = 0876884.sht.summary.dgn	USER NAME = thompsrd	DESIGNED GC	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>SUMMARY OF QUANTITIES</b>			F.A.P. RTE	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
	MODEL NAME = \$MODELNAME\$	DRAWN RDT	REVISED -		SCALE: NONE	SHEET NO. 2 OF 5 SHEETS	STA. -----	TO STA. -----	103	27-1-VHB-1	ST. CLAIR	277	4
	PLOT SCALE = 20.000 / IN.	CHECKED JAP	REVISED -		CONTRACT NO. 76884								
	PLOT DATE = 10/20/2011	DATE 10-19-11	REVISED -		ILLINOIS FED. AID PROJECT								