

SUMMARY OF QUANTITIES												
ITEM #	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	0004	0005	0011	0011	0011	0011	0040	0040	0040
				ROADWAY IL RTE 15	RESURFACING	BRIDGE SN 082-0117	BRIDGE SN 082-0118	BRIDGE SN 082-0119	BRIDGE SN 082-0120	MSE RET WALL SN 082-W311	MSE RET WALL SN 082-W312	MSE RET WALL SN 082-W313
X0327139	AGGREGATE COLUMN GROUND IMPROVEMENT	L SUM	1	1								
X2070304	POROUS GRANULAR EMBANKMENT, SPECIAL	CU YD	333			174	159					
X4810100	TEMPORARY SHOULDERS	SQ YD	979	979								
X5030305	CONCRETE WEARING SURFACE, 5"	SQ YD	558			279	279					
X6660445	RIGHT OF WAY AND PROPERTY CORNERS	EACH	2	2								
X7830070	GROOVING FOR RECESSED PAVEMENT MARKING 5"	FOOT	6,020.5	6,020.5								
Z0013796	SEDIMENT CONTROL, STABILIZED CONSTRUCTION ENTRANCE	SQ YD	500	500								
Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1								
Z0016002	DECK SLAB REPAIR (FULL DEPTH, TYPE II)	SQ YD	141	141								
Z0016200	DECK SLAB REPAIR (PARTIAL)	SQ YD	47	47								
Z0016702	DETOUR SIGNING	L SUM	1	1								
Z0018002	DRAINAGE SCUPPERS, DS-11	EACH	1			1						
Z0018800	DRAINAGE SYSTEM	L SUM	1			1						
Z0026407	TEMPORARY SHEET PILING	SQ FT	2,153			1,458		695				
Z0030260	IMPACT ATTENUATORS, TEMPORARY (FULLY REDIRECTIVE, NARROW), TEST LEVEL 3	EACH	3	3								
Z0030330	IMPACT ATTENUATORS, RELOCATE (FULLY REDIRECTIVE), TEST LEVEL 3	EACH	3	3								
Z0034210	MECHANICALLY STABILIZED EARTH RETAINING WALL	SQ FT	18,672			674				7835	5405	4758
Z0046304	PIPE UNDERDRAINS FOR STRUCTURES 4"	FOOT	180			90	90					
Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1	1								
Z0065704	BITUMINOUS COATED AGGREGATE SLOPEWALL 6"	SQ YD	10,512			4,910	5,602					
Z0065760	SLOTTED DRAIN 15" WITH VARIABLE SLOT	FOOT	193	193								
Z0065765	SLOTTED DRAIN 18" WITH VARIABLE SLOT	FOOT	386	386								
Z0065780	SLOTTED DRAIN 30" WITH VARIABLE SLOT	FOOT	649	649								
+ Z0076600	TRAINERS	HOUR	4,000	4,000								
Z0073100	TEMPORARY SHORING	EACH	3	3								

\* DENOTES SPECIALTY ITEM  
+ 0842

FILE NAME = 0676884-sht-summary.dgn	USER NAME = thompson	DESIGNED GC	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>SUMMARY OF QUANTITIES</b>	F.A.P. RTE	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
MODEL NAME = #MODELNAME#	DRAWN RDT	REVISED -	103			27-1-VHB-1	ST. CLAIR	277	7	
PLOT SCALE = 20.000 / IN.	CHECKED JAP	REVISED -	CONTRACT NO. 76884							
PLOT DATE = 10/20/2011	DATE 10-19-11	REVISED -	ILLINOIS FED. AID PROJECT							
				SCALE: NONE SHEET NO. 5 OF 5 SHEETS STA. ----- TO STA. -----						