SUMMARY OF QUANTITIES

RURAL - JACKSON COUNTY
HBP FUNDING
80% FEDERAL; 20% STATE
CONSTRUCTION TYPE CODE 0011
SN 039-0074

	CODE NUMBER	ITEM DESCRIPTION	UNIT	QUANTITY
	70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1
	70100500	TRAFFIC CONTROL AND PROTECTION, STANDARD 701326	L SUM	1
	70101830	TRAFFIC CONTROL AND PROTECTION, STANDARD BLR 21	L SUM	1
	70103815	TRAFFIC CONTROL SURVEILLENCE	CAL DA	3
	70106800	CHANGEABLE MESSAGE SIGN	CAL MO	1
	70300100	SHORT - TERM PAVEMENT MARKING	FOOT	4957
	70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	110986
	70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	2755
*	78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	110986
*	78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	25
*	78200410	GUARDRAIL MARKERS, TYPE A	EACH	14
*	78200520	BARRIER WALL MARKERS, TYPE B	EACH	12
*	78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	4
*	A2002714	TREE, CARYA OVATA (SHAGBARK HICKORY), 1-3/4" CALIPER, BALLED AND BURLAPPED	EACH	18
*	A2006514	TREE, QUERCUS BICOLOR (SWAMP WHITE OAK), 1-3/4" CALIPER, BALLED AND BURLAPPED	EACH	15
*	A2006914	TREE, QUERCUS PALUSTRIS (PIN OAK), 1-3/4" CALIPER, BALLED AND BURLAPPED	EACH	12
*	A2016814	TREE, QUERCUS SHUMARDII (SHUMARD RED OAK), 1-3/4" CALIPER, BALLED AND BURLAPPED	EACH	15
	X2020110	GRADING AND SHAPING SHOULDERS	UNIT	510
	X2070304	POROUS GRANULAR EMBANKMENT, SPECIAL	CU YD	174
	X542A497	PIPE CULVERTS, CLASS A, TYPE 1 EQUIVALENT ROUND-SIZE 42" TEMPORARY	FOOT	11
	Z0001900	ASBESTOS BEARING PAD REMOVAL	EACH	132
	Z0018002	DRAINAGE SCUPPERS, DS-11	EACH	2
	Z0046304	PIPE UNDERDRAINS FOR STRUCTURES 4"	FOOT	107
	Z0055905	TEMPORARY CONSTRUCTION FENCE	FOOT	1100
+	Z0076600	TRAINEES	HOUR	1000

+ 0042
* SPECIALTY ITEM

USER NAME = porterwc	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION
	DRAWN -	REVISED -	
PLOT SCALE = 50.0000 ' / in.	CHECKED -	REVISED -	
PLOT DATE = 11/3/2011	DATE -	REVISED -	

SUMMARY OF QUANTITIES

SCALE: SHEET NO. OF SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
686	114B-1	JACKSON	114	4

CONTRACT NO. 78049

ILLINOIS FED. AID PROJECT

FILE NAME = c:\pw_work\pwidot\porterwc\dms41786\78049-sht-pln.dgn