

WILLIAMSON COUNTY							
F. A. I. 57 ( I-57)				F. A. P. 331 ( IL 13)			
90% FEDERAL / 10% STATE				80% FEDERAL / 20% STATE			
ROADWAY	BRIDGE	BRIDGE	BRIDGE	LIGHTING	ROADWAY	SIGNALS	LIGHTING
STA. 403+50 TO STA. 1+00.79	100-0088 100-0089	100-0097	100-0098		STA. 1798+50 TO STA. 840+15.82	SINGLE POINT INTERSECTION	

URBAN

CODE NO.	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	CONSTRUCTION TYPE CODE								
				0003	0010	0008	0008	0021	0003	0021	0021	
* 63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	4	2						2		
* 63100169	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) FLARED	EACH	10	9						1		
63200310	GUARDRAIL REMOVAL	FOOT	4,999	4,758						241		
63200400	CABLE ROAD GUARD REMOVAL	FOOT	1,045	1,045								
63500105	DELINEATORS	EACH	245	245								
63700275	CONCRETE BARRIER, DOUBLE FACE, 42 INCH HEIGHT	FOOT	5,682	5,682								
63801200	MODULAR GLARE SCREEN SYSTEM	FOOT	4,229	4,229								
64200116	SHOULDER RUMBLE STRIPS, 16 INCH	FOOT	26,946	26,946								
64300430	IMPACT ATTENUATORS (NON-REDIRECTIVE), TEST LEVEL 2	EACH	4							4		
64300450	IMPACT ATTENUATORS (NON-REDIRECTIVE), TEST LEVEL 3	EACH	4	4								
64300530	IMPACT ATTENUATORS (PARTIALLY REDIRECTIVE), TEST LEVEL 3	EACH	1	1								
64301090	ATTENUATOR BASE	SQ YD	112	112								
66600105	FURNISHING AND ERECTING RIGHT OF WAY MARKERS	EACH	11	11								
66700205	PERMANENT SURVEY MARKERS, TYPE I	EACH	5	5								
66700305	PERMANENT SURVEY MARKERS, TYPE II	EACH	3	3								
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	30	30								
67100100	MOBILIZATION	L SUM	1	1								
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	910	610						300		
70106700	TEMPORARY RUMBLE STRIPS	EACH	3	3								
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	420	210						210		
70200100	NIGHTTIME WORK ZONE LIGHTING	L SUM	1	1								
70300100	SHORT TERM PAVEMENT MARKING	FOOT	8,452	6,100						2,352		
70300210	TEMPORARY PAVEMENT MARKING LETTERS AND SYMBOLS	SQ FT	1,061	482						579		
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	273,433	187,997						85,436		
70300230	TEMPORARY PAVEMENT MARKING - LINE 5"	FOOT	9,860	9,860								

\*SPECIALTY ITEM

FILE NAME = ...D978182-sht-S00.008.dgn	USER NAME = Matt Overbey	DESIGNED - MJO	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>SUMMARY OF QUANTITIES I-57 AND IL ROUTE 13</b>				F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	PLOT SCALE = 50.0000' / IN.	DRAWN - EEG	REVISED -		SCALE: N/A	SHEET NO.	OF	SHEETS	STA. N/A	TO STA. N/A	WILLIAMSON	968	12
	PLOT DATE = 10/19/2011	CHECKED - BJD	REVISED -								* F.A.I. 57 AND F.A.P. 331	CONTRACT NO. 78182	
		DATE - 10/07/11	REVISED -								ILLINOIS FED. AID PROJECT		