

WILLIAMSON COUNTY							
F. A. I. 57 (I-57)				F. A. P. 331 (IL 13)			
90% FEDERAL / 10% STATE				80% FEDERAL / 20% STATE			
ROADWAY	BRIDGE	BRIDGE	BRIDGE	LIGHTING	ROADWAY	SIGNALS	LIGHTING
STA. 403+50 TO STA. 1+00.79	100-0088 100-0089	100-0097	100-0098		STA. 1798+50 TO STA. 840+15.82	SINGLE POINT INTERSECTION	

URBAN

CODE NO.	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	CONSTRUCTION TYPE CODE								
				0003	0010	0008	0008	0021	0003	0021	0021	
81500100	GULFBOX JUNCTION	EACH	2								2	
* 81603000	UNIT DUCT, 600V, 2-1C NO. 8, 1/C NO. 8 GROUND, (XLP-TY. USE), 3/4" DIA. POLY.	FOOT	7,819					5,479				2,340
* 81603030	UNIT DUCT, 600V, 2-1C NO. 4, 1/C NO. 6 GROUND, (XLP-TY. USE), 1" DIA. POLY.	FOOT	10,795					4,860				5,935
* 81603040	UNIT DUCT, 600V, 2-1C NO. 6, 1/C NO. 8 GROUND, (XLP-TY. USE), 1" DIA. POLY.	FOOT	9,239					7,449				1,790
* 81702120	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO. 8	FOOT	968					968				
* 81702130	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE) 1/C NO. 6	FOOT	794					794				
* 82102250	LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, 250 WATT	EACH	114					50				64
* 82102400	LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, 400 WATT	EACH	13					13				
* 82104000	LUMINAIRE, SODIUM VAPOR, MULTI-MOUNT, 400 WATT	EACH	6					3				3
* 82107300	UNDERPASS LUMINAIRE, 150 WATT, HIGH PRESSURE SODIUM VAPOR	EACH	10					10				
* 82500360	LIGHTING CONTROLLER, BASE MOUNTED, 480VOLT, 100AMP	EACH	1					1				
* 82500380	LIGHTING CONTROLLER, BASE MOUNTED, 480VOLT, 200AMP	EACH	1					1				
* 83009300	LIGHT POLE, ALUMINUM, 45 FT. M. H., 8 FT. MAST ARM	EACH	4					4				
* 83009600	LIGHT POLE, ALUMINUM, 45 FT. M. H., 15 FT. MAST ARM	EACH	114					50				64
* 83010600	LIGHT POLE, ALUMINUM, 50 FT. M. H., 15 FT. MAST ARM	EACH	9					9				
* 83062735	LIGHT POLE, WEATHERING STEEL, 45 FT. M. H., TENON MOUNT - TWIN	EACH	1					1				
* 83062855	LIGHT POLE, WEATHERING STEEL, 45 FT. M. H., SHORT BRACKET - 2 FT.	EACH	1								1	
* 83600357	LIGHT POLE FOUNDATION, METAL, 15" BOLT CIRCLE, 8" X 8'	EACH	137					137				
* 83800650	BREAKAWAY DEVICE, COUPLING WITH STAINLESS STEEL SCREEN	EACH	480					220				260
84200600	REMOVAL OF LIGHTING UNIT, NO SALVAGE	EACH	24					16				8
84200804	REMOVAL OF POLE FOUNDATION	EACH	34	2				24				8
84400105	RELOCATE EXISTING LIGHTING UNIT	EACH	13					13				
84500110	REMOVAL OF LIGHTING CONTROLLER	EACH	2					2				
84500120	REMOVAL OF ELECTRIC SERVICE INSTALLATION	EACH	2					2				
84500130	REMOVAL OF LIGHTING CONTROLLER FOUNDATION	EACH	2					2				

\* SPECIALTY ITEM

FILE NAME = ...D978182-shr-500_012.dgn	USER NAME = Matt Overbey	DESIGNED - MJO	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>SUMMARY OF QUANTITIES I-57 AND IL ROUTE 13</b>				F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	PLOT SCALE = 50.0000' / IN.	DRAWN - EEG	REVISED -		SCALE: N/A	SHEET NO.	OF	SHEETS	STA. N/A	TO STA. N/A	WILLIAMSON	968	16
	PLOT DATE = 10/19/2011	CHECKED - BJD	REVISED -								* F.A.I. 57 AND F.A.P. 331	CONTRACT NO. 78182	
		DATE - 10/07/11	REVISED -								[ILLINOIS] FED. AID PROJECT		