

**PIPE UNDERDRAINS (CONTINUED)**

LOCATION				PIPE UNDERDRAINS 4"	PIPE UNDERDRAINS 4" (SPECIAL)	CONCRETE HEADWALLS FOR PIPE DRAINS
STATION	TO	STATION		(FOOT)	(FOOT)	(EACH)
19+50.00			RT		26	2
19+50.00	-	21+97.60	LT	235		
19+50.00	-	21+24.36	RT	175		
<b>RAMP B-R</b>						
0+00.00	-	0+99.99	RT	100		
0+99.99			RT		26	2
0+99.99	-	4+25.56	RT	325		
1+53.34			LT		11	1
1+53.34	-	3+32.24	LT	198		
<b>RAMP C</b>						
0+55.39	-	3+00.00	LT	239		
1+34.89	-	3+00.00	RT	166		
3+00.00			RT		32	2
3+00.00	-	3+87.33	RT	88		
3+00.00			LT		32	2
3+00.00	-	7+19.62	LT	389		
4+66.80	-	7+37.99	RT	272		
7+19.62			LT		11	1
7+19.62	-	11+09.38	LT	388		
7+37.99			RT		13	1
7+37.99	-	10+93.98	RT	356		
10+93.98			RT		13	1
10+93.98	-	15+50.00	RT	456		
11+09.38			LT		11	1
11+09.38	-	15+00.00	LT	392		
15+50.00			RT		24	2
15+50.00	-	19+14.97	RT	365		
19+14.97			RT		16	1
19+14.97	-	22+26.84	RT	312		
<b>RAMP C-R</b>						
0+00.00	-	2+50.00	RT	250		
0+91.68	-	2+45.88	LT	170		
2+45.88			LT		11	1
2+50.00			RT		32	2
2+50.00	-	3+35.41	RT	85		
<b>RAMP D</b>						
112+50.00	-	116+90.25	RT	441		
112+50.00	-	117+40.91	LT	497		
116+90.25			RT		13	1
116+90.25	-	121+80.23	RT	500		
117+40.91			LT		11	1
117+40.91	-	122+66.32	LT	500		
121+80.23			RT		13	1
121+80.23	-	122+52.77	RT	76		
122+66.32			LT		11	1
122+66.32	-	128+00.00	LT	500		
123+70.27	-	128+00.00	RT	431		
128+00.00			LT		22	2
128+00.00	-	130+00.64	LT	201		
128+00.00			RT		26	2
128+00.00	-	129+35.76	RT	136		
<b>RAMP D-R</b>						
0+00.00	-	4+25.00	RT	425		
1+17.80	-	4+25.00	LT	320		
4+25.00			LT		22	2
4+25.00	-	5+27.09	LT	113		
4+25.00			RT		26	2
4+25.00	-	6+22.17	RT	197		
<b>RAMP I</b>						
13+02.05			LT		11	1
13+02.05	-	13+29.46	LT	28		
13+02.05			RT		13	1
13+02.05	-	13+41.74	RT	40		
15+23.64	-	20+00.00	LT	477		
15+35.92	-	18+07.68	RT	272		
18+07.68			RT		13	1
18+07.68	-	21+00.00	RT	293		
20+00.00			LT		11	1
<b>SUBTOTALS</b>				10,408	450	35

**PIPE UNDERDRAINS (CONTINUED)**

LOCATION				PIPE UNDERDRAINS 4"	PIPE UNDERDRAINS 4" (SPECIAL)	CONCRETE HEADWALLS FOR PIPE DRAINS
STATION	TO	STATION		(FOOT)	(FOOT)	(EACH)
21+00.00			RT		26	2
21+00.00	-	23+35.10	RT	236		
<b>RAMP J</b>						
3+86.70	-	6+00.00	RT	214		
4+54.82	-	5+50.00	LT	98		
5+50.00			LT		24	2
5+50.00	-	8+75.73	LT	333		
6+00.00			RT		26	2
6+00.00	-	8+62.15	RT	263		
11+50.00	-	15+87.05	LT	434		
11+50.00	-	16+45.49	RT	500		
15+87.05			LT		11	1
15+87.05	-	19+50.00	LT	353		
16+45.49			RT		14	1
16+45.49	-	19+94.56	RT	358		
19+50.00			LT		11	1
19+50.00	-	19+94.56	LT	45		
19+94.56			RT		13	1
<b>TOTALS</b>				51,930	1,950	106