

TEMPORARY CONCRETE BARRIER WALL

STATION / LOCATION			TEMPORARY CONCRETE BARRIER	RELOCATE TEMPORARY CONCRETE BARRIER	TEMPORARY CONCRETE BARRIER, STATE OWNED	RELOCATE TEMPORARY CONCRETE BARRIER, STATE OWNED	MODULAR GLARE SCREEN SYSTEM	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TL2	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TL3	IMPACT ATTENUATORS, TEMPORARY (FULLY REDIRECTIVE, NARROW), TL2	IMPACT ATTENUATORS, TEMPORARY (FULLY REDIRECTIVE, NARROW) TL3	IMPACT ATTENUATORS, RELOCATE (FULLY REDIRECTIVE, NARROW), TL2	IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TL2	IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TL3	MONODIRECTIONAL PRISMATIC BARRIER REFLECTOR
STATION	TO	STATION	(FOOT)	(FOOT)	(FOOT)	(FOOT)	(FOOT)	(EACH)	(EACH)	(EACH)	(EACH)	(EACH)	(EACH)	(EACH)	(EACH)
PRE-STAGE A															
F. A. I. 57															
11+68.41	(RAMP C)	-	1510+00.00		948				1						10
1510+00.00		-	1513+08.43		315										4
PRE-STAGE A SUBTOTALS			0	0	1,263	0	0	0	1	0	0	0	0	0	14
PRE-STAGE B															
F. A. I. 57															
1463+40.18		-	1471+00.00		760				1						8
1471+00.00		-	1485+00.00		1,408										14
1485+00.00		-	1497+00.00		1,203										12
1497+00.00		-	1510+00.00		1,747	948								1	18
1510+00.00		-	1513+71.72		369	315			1						4
IL 13															
1797+54.79		-	1805+00.00		1,142			2		1					12
1805+00.00		-	1819+00.00	4,079	71					1					55
1819+00.00		-	833+00.00	1,612						3					19
833+00.00		-	840+74.79	1,492						2					23
TEMPORARY RAMP A															
13+35.75		-	20+64.27		744				1						8
PRE-STAGE B SUBTOTALS			7,183	0	7,444	1,263	0	2	3	7	0	0	0	1	173
STAGE 1															
F. A. I. 57															
1461+16.07		-	1471+00.00			1,721	988								10
1471+00.00		-	1485+00.00		77	1,863	1,408								16
1485+00.00		-	1497+00.00	825	628		1,203								27
1497+00.00		-	1510+00.00	3,945			630								47
1510+00.00		-	1520+00.00	1,320							1			1	14
RAMP D															
113+92.00		-	115+83.79		338						2				4
TEMPORARY RAMP A															
12+81.94		-	19+83.11			744								1	
STAGE 1A															
IL 13															
1819+00.00		-	833+00.00	100				1							2
STAGE 1B															
IL 13															
1797+78.40		-	1803+62.65			1,084						1	1		
1805+38.07		-	1819+00.00		3,355	129						2	1		
1819+00.00		-	833+00.00		2,409			1				1			
833+00.00		-	840+87.53		1,153			1							
STAGE 1 SUBTOTALS			6,190	6,917	1,043	5,541	4,229	3	0	0	3	4	2	3	120
STAGE 2															
F. A. I. 57															
402+50.66		-	415+00.00			1,251			1						
415+00.00		-	1464+08.86			782									
1474+41.51		-	1485+00.00			1,182			2						
1485+00.00		-	1497+00.00			1,208									
1497+56.52		-	1510+00.00			2,115			1					1	
1510+00.00		-	1511+04.46			190								1	
IL 13															
1809+37.62		-	1818+18.98		951	1,213							3		
STAGE 2 SUBTOTALS			0	951	0	7,941	0	0	4	0	0	0	3	2	0