



**TEMPORARY DIAMOND CONNECTIONS - PRE-STAGE A**  
 TEMP. RAMP A: STA. 13+45.00 TO STA. 19+81.80

**NOTES:**  
 1. CONTRACTOR TO VERIFY HORIZONTAL AND VERTICAL LOCATION OF TEMPORARY DIAMOND STUBS TO DETERMINE IF FIELD ADJUSTMENTS TO CURVES OR ELEVATIONS ARE REQUIRED. CONTRACTOR SHALL RECEIVE APPROVAL FROM RESIDENT ENGINEER PRIOR TO CONSTRUCTING TEMPORARY DIAMOND CONNECTORS.

**TEMP. DIAMOND A COORDINATE DATA**

P.R.C. STA. 15+36.77  
 N: 392047.274  
 E: 804239.273  
 P.C.C. STA. 17+46.01  
 N: 392219.912  
 E: 804121.664  
 P.T. STA. 19+83.11  
 N: 392446.670  
 E: 804060.084

**TEMP. DIAMOND A CURVES**

PROP. CURVE DIAA3 PI STA. = 16+41.74 Δ = 11° 30' 20" (RT) D = 5° 29' 55" R = 1,042.00' T = 104.97' L = 209.24' E = 5.27' e = N/C T.R. = N/A S.E. RUN = N/A P.R.C. STA = 15+36.77 P.C.C. STA = 17+46.01	PROP. CURVE DIAA4 PI STA. = 18+66.75 Δ = 26° 38' 13" (RT) D = 11° 14' 04" R = 510.00' T = 120.73' L = 237.10' E = 14.10' e = N/C T.R. = N/A S.E. RUN = N/A P.C.C. STA = 17+46.01 P.T. STA = 19+83.11
--	--

**NOTES:**  
 1. CONTRACTOR TO VERIFY HORIZONTAL AND VERTICAL LOCATION OF TEMPORARY DIAMOND STUBS TO DETERMINE IF FIELD ADJUSTMENTS TO CURVES OR ELEVATIONS ARE REQUIRED. CONTRACTOR SHALL RECEIVE APPROVAL FROM RESIDENT ENGINEER PRIOR TO CONSTRUCTING TEMPORARY DIAMOND CONNECTORS.

**LEGEND**

- WORK ZONE
- COMPLETED PAVEMENT
- TEMPORARY PAVEMENT - FULL DEPTH (CONSTRUCTED THIS STAGE)
- TEMPORARY PAVEMENT - FULL DEPTH (CONSTRUCTED PREVIOUS STAGE)
- TEMPORARY RAMP
- MILL/OVERLAY
- TEMPORARY CONCRETE BARRIER WALL
- IMPACT ATTENUATORS, TEMPORARY (FULLY REDIRECTIVE, NARROW)
- IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE)
- DRUM WITH STEADY BURNING LIGHT
- TYPE II BARRICADE WITH STEADY BURNING LIGHT
- TYPE III BARRICADE WITH FLASHING LIGHTS
- DIRECTION OF TRAFFIC FLOW