

copy from

| CODE NO. | ITEM DESCRIPTION  | UNIT   | TOTAL QUANTITY | UNION COUNTY |                                     |
|----------|---|--------|----------------|--------------|-------------------------------------|
|          |   |        |                | STP FUNDING  | CONST. CODE 0040<br>SN 091-7090 (P) |
| 20100110 | TREE REMOVAL (6 TO 15 UNITS DIAMETER)                     | UNIT   | 25             |              |                                     |
| 20700220 | POROUS GRANULAR EMBANKMENT                                | CU YD  | 406            |              |                                     |
| 25000115 | SEEDING, CLASS 1B   | ACRE   | 0.1            |              |                                     |
| 25000350 | SEEDING, CLASS 7  | ACRE   | 0.1            |              |                                     |
| 25000400 | NITROGEN FERTILIZER NUTRIENT                              | POUND  | 9              |              |                                     |
| 25000500 | PHOSOPHORUS FERTILIZER NUTRIENT                           | POUND  | 9              |              |                                     |
| 25000600 | POTASSIUM FERTILIZER NUTRIENT                             | POUND  | 9              |              |                                     |
| 25000700 | AGRICULTURAL GROUND LIMESTONE                             | TON    | 0.2            |              |                                     |
| 25100115 | MULCH, METHOD 2   | ACRE   | 0.1            |              |                                     |
| 28100707 | STONE DUMPED RIPRAP, CLASS A4                             | SQ YD  | 12             |              |                                     |
| 40200100 | AGGREGATE SURFACE COURSE, TYPE A                          | TON    | 13             |              |                                     |
| 40300100 | BITUMINOUS MATERIALS (PRIME COAT)                         | GALLON | 103            |              |                                     |
| 40603245 | POLYMERIZED HOT-MIX ASPHALT BINDER COURSE, IL 19.0, N105  | TON    | 71             |              |                                     |
| 40603550 | POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N105 | TON    | 18             |              |                                     |
| 42300100 | PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 5 INCH        | SQ YD  | 58             |              |                                     |
| 42400100 | PORTLAND CEMENT CONCRETE SIDEWALK 4 INCH                  | SQ FT  | 592            |              |                                     |
| 44000100 | PAVEMENT REMOVAL  | SQ YD  | 206            |              |                                     |
| 44000200 | DRIVEWAY PAVEMENT REMOVAL                                 | SQ YD  | 54             |              |                                     |
| 44000500 | COMBINATION CURB AND GUTTER REMOVAL                       | FOOT   | 99             |              |                                     |
| 44000600 | SIDEWALK REMOVAL  | SQ FT  | 539            |              |                                     |
| 50100100 | REMOVAL OF EXISTING STRUCTURES                            | EACH   | 1              |              |                                     |
| 50200100 | STRUCTURE EXCAVATION                                      | CU YD  | 681            |              |                                     |
| 50800205 | REINFORCEMENT BARS (EPOXY COATED)                         | POUND  | 1080           |              |                                     |

| CODE NO. | ITEM DESCRIPTION   | UNIT   | TOTAL QUANTITY | UNION COUNTY |                                     |
|----------|--|--------|----------------|--------------|-------------------------------------|
|          |  |        |                | STP FUNDING  | CONST. CODE 0040<br>SN 091-7090 (P) |
| 50901720 | BICYCLE RAILING  | FOOT   | 55             |              |                                     |
| 54003000 | CONCRETE BOX CULVERTS                                    | CU YD  | 14.1           |              |                                     |
| 54011004 | PRECAST CONCRETE BOX CULVERTS 10' X 4'                   | FOOT   | 86             |              |                                     |
| 54248510 | CONCRETE COLLAR  | CU YD  | 5.7            |              |                                     |
| 550A0120 | STORM SEWER, CLASS A, TYPE 1 24"                         | FOOT   | 11             |              |                                     |
| 550A0190 | STORM SEWER, CLASS A, TYPE 1 48"                         | FOOT   | 64             |              |                                     |
| 55101200 | STORM SEWER REMOVAL 24"                                  | FOOT   | 6              |              |                                     |
| 55101900 | STORM SEWER REMOVAL 48"                                  | FOOT   | 18             |              |                                     |
| 60224030 | MANHOLES, TYPE A, 6' -DIAMETER, TYPE 15 FRAME AND LID    | EACH   | 1              |              |                                     |
| 60224446 | MANHOLES, TYPE A, 7' -DIAMETER, TYPE 1 FRAME, CLOSED LID | EACH   | 1              |              |                                     |
| 60224459 | MANHOLES, TYPE A, 8' -DIAMETER, TYPE 1 FRAME, CLOSED LID | EACH   | 1              |              |                                     |
| 60404800 | FRAMES AND GRATES, TYPE 11                               | EACH   | 1              |              |                                     |
| 60605000 | COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24        | FOOT   | 99             |              |                                     |
| 67100100 | MOBILIZATION   | L SUM  | 1              |              |                                     |
| 70101830 | TRAFFIC CONTROL AND PROTECTION, STANDARD BLR 21          | L SUM  | 1              |              |                                     |
| 70102622 | TRAFFIC CONTROL AND PROTECTION, STANDARD 701502          | L SUM  | 1              |              |                                     |
| 70103815 | TRAFFIC CONTROL SURVEILLANCE                             | CAL DA | 40             |              |                                     |
| 70106800 | CHANGEABLE MESSAGE SIGN                                  | CAL MO | 1              |              |                                     |
| 70300100 | SHORT TERM PAVEMENT MARKING                              | FOOT   | 16             |              |                                     |
| 70300220 | TEMPORARY PAVEMENT MARKING - LINE 4"                     | FOOT   | 103            |              |                                     |
| 78001110 | PAINT PAVEMENT MARKING - LINE 4"                         | FOOT   | 103            |              |                                     |
| Z0055905 | TEMPORARY CONSTRUCTION FENCE                             | FOOT   | 200            |              |                                     |