

EROSION CONTROL SCHEDULE

STATION	STATION	OFFSET	TEMP EROS CONTR SEED (POUND)	TEMP DITCH CHECKS (FOOT)	PERIMETER EROS BAR (FOOT)	INLET & PIPE PROTECTION (EACH)
NORTH SEVEN HILLS ROAD						
46+88	58+00	RT/LT	60		198	
46+88	49+25	RT		20		
47+00	48+80	RT				
48+06	49+34	LT			173	
48+25		35' RT				1
48+28		15' LT				1
48+28		20' RT				1
48+38		15' LT				1
48+38		21' RT				1
48+80		15' LT				1
48+80		22' RT				1
49+16		27' RT				1
49+18		21' LT				1
50+60	52+83	RT			161	
50+76	58+02	LT			734	
50+91		23' RT				1
51+20		19' LT				1
51+20		19' RT				1
51+30		18' LT				1
51+30		18' RT				1
OLD VINCENNES TRAIL						
113+22	119+41	RT/LT	100			
113+22	115+25	RT			210	
113+22	116+00	LT			321	
115+15		22' LT				1
115+15		15' RT				1
115+27		22' LT				1
115+27		14' RT				1
115+58		19' RT				1
115+59		25' LT				1
116+80	119+41	RT			302	
117+17	119+41	LT			225	
117+25	118+50	LT		95		
117+35		20' RT				1
117+36		21' LT				1
117+90		18' RT				1
118+50		30' RT				1
118+75		16' LT				1
118+75		16' RT				1
TOTAL			160	115	2324	26

EARTHWORK SCHEDULE

STATION	STATION	EARTH EXCAVATION (CU YD)	EARTH EXCAVATION ADJUSTED FOR SHRINKAGE (CU YD)	EMBANKMENT (CU YD)	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-) (CU YD)
NORTH SEVEN HILLS ROAD					
46+87.93	58+00.00	1490	1118	305	813
OLD VINCENNES TRAIL					
113+21.96	119+40.53	1855	1392	570	822
TOTAL		3345	2510	875	1635

EARTHWORK NOTES:

1. ESTIMATED SHRINKAGE FACTOR = 25%.
2. APPROXIMATE EMBANKMENT QUANTITY IS SHOWN FOR INFORMATION ONLY.
3. APPROXIMATE EARTHWORK BALANCE IS SHOWN FOR INFORMATION ONLY.

SEEDING SCHEDULE

STATION	STATION	TOPSOIL F&P VAR DP (SO YD)	SEEDING CL 2 (ACRE)	NITROGEN FERT NUTR (POUND)	PHOSPHORUS FERT NUTR (POUND)	POTASSIUM FERT NUTR (POUND)	MULCH METHOD 2 (ACRE)
NORTH SEVEN HILLS ROAD							
46+87.93	58+00.00		0.30	27	27	27	0.30
49+69.46	50+33.46	161.5					
OLD VINCENNES TRAIL							
113+21.96	119+40.53		0.45	40	40	40	0.45
116+15.36	116+79.36	161.5					
TOTAL		323	0.75	67	67	67	0.75

FILE NAME = 0629051-sht-schedule.dgn	USER NAME = joelitaliano	DESIGNED -	REVISED -
	PLOT TIME = 9:14:03 AM	DRAWN -	REVISED -
	PLOT SCALE = 48.0000' / IN.	CHECKED -	REVISED -
	PLOT DATE = 10/9/2011	DATE -	REVISED -

CITY OF O'FALLON

SCHEDULE OF QUANTITIES

SCALE: NONE SHEET NO. 02 OF 03 SHEETS STA. TO STA.

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
9172	10-00036-03-PV	ST CLAIR	51	12
CONTRACT NO. 97478				