


ROUTE	SECTION	COUNTY	TOWNSHIP	TOTAL SHEETS	SHEET NUMBER
FAS 1919	06-00144-00-WR	JACKSON	MAKANDA	91	33
JOB NO. C-99-579-06			PROJECT NO. SR-1919(106)		
BOSKYDELL ROAD			CONTRACT NO. 99338		

78+00      79+00      80+00      81+00      82+00      83+00      84+00



SE 1/4 SW 1/4 SEC 2

EAST LINE SE 1/4 SW 1/4 SEC. 2

EAST LINE N.E. 1/4, N.W. 1/4 SEC. 11

NOTE: CONTRACTOR TO WARP FLOWLINE ELEVATION OF GUTTER ON LEFT BETWEEN STA. 78+25' AND STA. 80+00'. SEE ELEVATIONS THIS SHEET. ALSO NOTE THAT PEAK OF GUTTER IS AT STA. 78+87.5

INSTALL 158' - 42" RCCP, TYPE 4 & 2 - 42" PRCF END SECTIONS  
 U.S. FL. - 440.00 @ STA. 82+37, 59.5' LT. (END SECTION)  
 D.S. FL. - 431.00 @ STA. 81+75, 103' RT. (END SECTION)  
 TRENCH BACKFILL - 120 CU. YDS.

REMOVE 58' - 42" CMP  
 TRENCH BACKFILL - 150 CU. YDS.

REMOVE 30' - 12" CMP  
 TRENCH BACKFILL - 10 CU. YDS.

CONC. BLOCK STEPS  
 W/ 4"X4" TIMBER POST

CONSTRUCTION LIMITS

CONSTRUCTION LIMITS

CONSTRUCTION LIMITS

TEMPORARY USE PERMIT

LEGEND

- |        |                            |         |                                  |
|--------|----------------------------|---------|----------------------------------|
| ⊕      | POWER POLE                 | ⊙       | PROPOSED TEMPORARY USE PERMIT    |
| ⊖      | POLE ANCHOR                | ⊙       | SURVEY MONUMENTS (FOUND)         |
| ⊙      | TELEPHONE POLE             | ⊙       | EXISTING RIGHT-OF-WAY MARKER     |
| TP ⊕   | TELEPHONE PEDESTAL         | —       | SIGN                             |
| ⊙      | TELEPHONE WARNING SIGN     | MB ⊙    | MAILBOX                          |
| CATV ⊕ | CABLE TELEVISION PEDESTAL  | RCP     | REINFORCED CONCRETE PIPE CULVERT |
| FH ⊕   | FIRE HYDRANT               | CMP     | CORRUGATED METAL PIPE CULVERT    |
| WV ⊙   | WATER VALVE                | TC      | TOP OF CASTING / TOP OF CURB     |
| WM ⊙   | WATER METER                | INV.    | INVERT                           |
| —      | WATER LINE                 | FL      | FLOWLINE                         |
| GVO    | GAS VALVE                  | 500     | EXISTING CONTOUR                 |
| G      | GAS LINE                   | 500     | PROPOSED CONTOUR                 |
| —      | FIBER OPTIC LINE           | x500.00 | PROPOSED GRADE                   |
| —      | TREE/BRUSH LINE            | ⊗       | TREE REMOVAL (INDIVIDUAL)        |
| —      | FENCE LINE                 | ⊗       | TREE REMOVAL (AREA)              |
| —      | PROPERTY LINE              |         |                                  |
| —      | EXISTING RIGHT-OF-WAY LINE |         |                                  |
| —      | PROPOSED RIGHT-OF-WAY LINE |         |                                  |

CURVE NO. 6

Δ - 01°30'34"      P.C. - 83+08.41  
 R - 11,388.30'      P.I. - 84+58.42  
 L - 300.00'      P.R.C. - 86+08.41  
 T - 150.01'

NOTES

- THE EXISTENCE, POSITION, SIZE AND TYPE OF ALL UNDERGROUND UTILITIES ARE APPROXIMATE AS SHOWN, BEING LOCATED BY ELECTRONIC DETECTION EQUIPMENT, BY VISUAL OBSERVATION, FROM UTILITY COMPANY MAPS AND BY VERBAL TESTIMONY OF EMPLOYEES FROM APPROPRIATE UTILITY COMPANY. VERIFICATION OF THE EXISTENCE, POSITION, SIZE AND TYPE SHOULD BE REQUESTED THROUGH "JULIE", 1-800-892-0126 PRIOR TO ANY CONSTRUCTION.
- ALL PHYSICAL FEATURES DEPICTED BY THIS SURVEY WERE CONDITIONS AS OF OCTOBER, 2006.

JACKSON COUNTY HIGHWAY DEPARTMENT JACKSON COUNTY, ILLINOIS BOSKYDELL ROAD GRADING, STORM SEWER AND TREE REMOVAL PLAN STA. 78+00 TO STA. 84+00
---