CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE 0005 ROADWAY 90% FEDERAL 10% STATE RURAL-KNOX	0005 ROADWAY 90% FEDERAL 10% STATE RURAL-PEORIA	0005 ROADWAY 100% STATE RURAL KNOX COUNTY	0005 ROADWAY 100% STATE RURAL PEORIA COUNTY
Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	1			1	
Z0033600	LONGITUDINAL JOINT REPAIR	FOOT	586	586			
Z0034105	MATERIAL TRANSFER DEVICE	TON	62442	45966	16476		
Z0041500	PLUG EXISTING CULVERTS	EACH	2	2			
∅ Z0076600	TRAINEES	HOUR	1000	750	250		
∅ Z0076604	TRAINEES TRAINING PROGRAM GRADUATE	HOUR	1000	750	250		

4

∅ 0042

REV 1-6-17

• 48-[29RS-7,30RS-1];72-3RS-2

FILE NAME = D468507-sht-SQQ.dgn	USER NAME = kaithbr	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES	F.A.I RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
		DRAWN -	REVISED -			74	•	KNOX/PEORIA	124	12
	PLOT SCALE = 100.0000 ' / in.	CHECKED -	REVISED -					CONTRACT NO. 68507		
	PLOT DATE = 10/31/2016	DATE -	REVISED -					ILLINOIS FED. AID PROJECT		

LOCATION		LOCATION * (SEE PROP. DRAINAGE DETAILS SHEETS)	MEDIAN INLET (604106)	PIPE CULVERTS TO BE CLEANED, 24"	PIPE CULVERTS TO BE CLEANED, 72"	DRAINAGE STRUCTURES TO BE CLEANED	CLEAN EXISTING END SECTION	CONCRETE COLLAR	REINFORCEMENT BARS	INSERTION CULVERT LINER, 24"	CURED-IN-PLACE PIPE LINER, 36"	TRAVERSABLE PIPE GRATE	CAST-IN-PLACE REINFORCED CONC. END SECTION, 24"	METAL END SECTIONS 12"
STATION	MILE MARKER		EACH	FOOT	FOOT	EACH	EACH	CU. YD.	LBS.	FOOT	FOOT	EACH	EACH	EACH
LT. STA. 1072+00														
LT. STA. 1102+45 (S.N. 048-2001)		1				1								
STRUCTURE NO. 048-2004								2	140					
LT. STA. 1110+32	62.500	2								17				
STA. 465+50	62.700	3	1											
LT. STA. 478+00	62.900	4			390		1							
RT. STA. 475+45	62.900	5												
RT. STA.479+40	62.910	6												
STA. 489+20	63.140	7												
LT. STA. 501+00	63.370	8		88				0.5						
LT. STA. 513+00	63.590			88				0.5						
LT. STA. 820+00				88				0.5						
RT. STA. 576+00 TO 580+00	64.800	9		88										
COUNTY HIGHWAY 18 SOUTH BRIDGE CONE- LT. STA. 579+94	64.858										65			
COUNTY HIGHWAY 18 NORTH BRIDGE CONE- LT. STA. 579+94	64.858										65			
CENTER MEDIAN STA. 576+00 TO STA. 580+00	64.858													1
LT. STA. 586+00	64.990						1							
RT. STA. 606+10	65.370													
LT. STA. 659+25 TO 660+50	66.400	10												
RT. STA. 664+00 TO 667+30	66.400						1							
RT. STA. 676+90 TO 682+10	66.780	11												
LT. STA. 681+50 TO 683+00	66.780													
FRENCH CREEK														
CENTER MEDIAN STA. 685+50 TO 688+00	66.810													
RT. STA. 683+40														
RT. STA. 692+40 TO 695+50		12											1	
LT. STA. 696+00														
KNOX RD. 1000N NORTH BRIDGE CONE STA. 697+15	67.083										100			
KNOX RD. 1000N SOUTH BRIDGE CONE STA. 697+15	67.084										100			
RT. STA. 698+00														
LT. STA. 707+00	67.280			88										
RT. STA. 734+00	67.780			88										
STA. 747+50	68.040				248									
KNOX COUNTY TOTAL			1	528	638	1	3	3.5	140	17	330	7	1	1
PEORIA/KNOX COUNTY LINE														
IL 78 SOUTH BRIDGE CONE STATION 808+00	69.200										100			
STA. 820+00	69.410			88				0.5						
STA. 859+20	70.100						1							
PEORIA COUNTY TOTAL			0	88	0	0	1	0.5	0	0	100	7	0	0
REST AREA TABLE SUB-TOTAL									180					
PROJECT TOTAL			1	616	638	1	4	4	320	17	430	14	1	1

1 REV 1-6-17

FILE NAME = 0468507-sht-schedule.dgn	USER NAME = noltara	DESIGNED -	REVISED -
		DRAWN -	REVISED -
	PLOT SCALE = 40.0000 ' / in.	CHECKED -	REVISED -
Default	PLOT DATE = 1/6/2017	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

SCALE: | SHEET OF SHEETS | STA. | TO STA.

* 48-129RS-7,30RS-1,72-3RS-2

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
74	*	KNOX/PEORIA	124	19
		CONTRACT NO. 68507		
	ILLINOIS FED. AID PROJECT			