

SI	SP	CODE NO.	ITEM	UNIT	TOTAL QUANTITY	90% FED / 10% STATE		100% STATE	
						CONSTRUCTION CODE			
						0004 ROADWAY	0011 STRUCTURAL	0011 STRUCTURAL	0021 SIGNS/LIGHTING
	SN 048-0101 (WB)	SN 048-0102 (EB)							
		54213681	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 36"	EACH	2	2			
		5421A012	PIPE CULVERTS, CLASS A, TYPE 1 12" (TEMPORARY)	FOOT	49	49			
		5421A018	PIPE CULVERTS, CLASS A, TYPE 1 18" (TEMPORARY)	FOOT	562	562			
		5421A024	PIPE CULVERTS, CLASS A, TYPE 1 24" (TEMPORARY)	FOOT	851	851			
		542A1081	PIPE CULVERTS, CLASS A, TYPE 2 36"	FOOT	330	330			
		59100100	GEOCOMPOSITE WALL DRAIN	SQ YD	213		106	107	
		60100060	CONCRETE HEADWALLS FOR PIPE DRAINS	EACH	21	21			
		60108100	PIPE UNDERDRAINS 4" (SPECIAL)	FOOT	420	420			
		60108104	PIPE UNDERDRAINS, TYPE 1, 4"	FOOT	10,422	10,422			
		60108501	PIPE UNDERDRAINS, TYPE 3	FOOT	10,422	10,422			
		63000001	STEEL PLATE BEAM GUARDRAIL, TYPE A, 6 FOOT POSTS	FOOT	2,380.0	2,380.0			
		63100070	TRAFFIC BARRIER TERMINAL, TYPE 5	EACH	2	2			
		63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	4	4			
		63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	4	4			
		63200310	GUARDRAIL REMOVAL	FOOT	2,063	2,063			

NOTES: SP - SEE PROJECT SPECIFIC SPECIAL PROVISIONS
SI - SPECIALTY ITEM

REV. 1-6-17



USER NAME = kmthbr	DESIGNED -	REVISED -
PLOT SCALE = 100.0000' / 1"	DRAWN -	REVISED -
PLOT DATE = 10/28/2016	CHECKED -	REVISED -
	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: SHEET 5 OF 10 SHEETS STA. TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
74	(48-26HV)BR	KNOX	212	9
			CONTRACT NO. 68B69	
ILLINOIS FED. AID PROJECT				