

URBAN

URBAN

SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	0005 80% FED/ 20% STATE			
60262700	INLETS TO BE RECONSTRUCTED	EACH	3	3			
60300105	FRAMES AND GRATES TO BE ADJUSTED	EACH	8	8			
60300305	FRAMES AND LIDS TO BE ADJUSTED	EACH	7	7			
60406530	FRAMES AND LIDS, CLOSED LID (CITY OF CHICAGO)	EACH	5	5			
60600605	CONCRETE CURB TYPE B	FOOT	124	124			
* 66900200	NON SPECIAL WASTE DISPOSAL	CU YD	43	43			
* 66900450	SPECIAL WASTE PLANS AND REPORTS	L SUM	1	1			
* 66900530	SOIL DISPOSAL ANALYSIS	EACH	2	2			
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6			
67100100	MOBILIZATION	L SUM	1	1			
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1	1			
70102632	TRAFFIC CONTROL AND PROTECTION, STANDARD 701602	L SUM	1	1			
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1			
* SPECIALTY ITEMS							

SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	0005 80% FED/ 20% STATE			
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1	1			
70300100	SHORT TERM PAVEMENT MARKING	FOOT	22146	22146			
70300150	Short term pavement marking removal	SQ FT	7381	7381			
70300210	TEMPORARY PAVEMENT MARKING LETTERS AND YMBOLS	SO FT	338	338			
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	46364	46364			
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	6138	6138			
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	2450	2450			
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	272	272			
70300520	PAVEMENT MARKING TAPE, TYPE III, 4"	FOOT	11073	11073			
* 72000100	SIGN PANEL - TYPE 1	SO FT	38	38			
* 72800100	TELESCOPING STEEL SIGN SUPPORT	FOOT	7	7			
* 73100100	BASE FOR TELESCOPING STEEL SIGN SUPPORT	EACH	1	1			
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SO FT	291	291			
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	46364	46364			
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	6138	6138			

FILE NAME *	USER NAME *	DESIGNED -	REVISED -
PROJECT NO. / DISTRICT / PROJECT NO. / CONTRACT NO. / SHEET NO.		CHECKED -	REVISED -
		DATE -	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES			
SCALE:	SHEET NO. OF SHEETS	STA. TO STA.	

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
3513	2014-058-RS	COOK	30	3A
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT				

B

Rev. 1-04-17

URBAN

URBAN

SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	0005 80% FED/ 20% STATE			
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	2450	2450			
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	272	272			
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	248	248			
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	216	216			
* 85000200	MAINTENANCE OF EXISTING TRAFFIC SIGNAL INSTALLATION	EACH	3	3			
* 89502376	REBUILD EXISTING HANDHOLE	EACH	3	3			
X0320050	CONSTRUCTION LAYOUT (SPECIAL)	L SUM	1	1			
X0327980	<i>Pavement marking Removal - Water Blasting</i>	SQFT	3690	3690			
X4401198	HOT MIX ASPHALT SURFACE REMOVAL VARIABLE DEPTH	SO. YD.	2680	2680			
# X5537800	STORM SEWERS TO BE CLEANED 12"	FOOT	80	80			
# X5538000	STORM SEWERS TO BE CLEANED 18"	FOOT	60	60			
# X5538200	STORM SEWERS TO BE CLEANED 24"	FOOT	20	20			
X6030310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	67	67			
Z0004562	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	3187	3187			

SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	0005 80% FED/ 20% STATE			
# Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	54	54			
Z0030850	TEMPORARY INFORMATION SIGNING	SO FT	129	129			
	* DENOTES SPECIALTY ITEMS						
	# NON PARTICIPATING ITEMS (100% STATE)						

FILE NAME	USER NAME = oguall	DESIGNED -	REVISED -
OFFICIAL TITLE	OFFICIAL TITLE	CHECKED -	REVISED -
PLOT SCALE = 1/8" = 1'		DATE -	REVISED -
PLOT DATE = 11/3/2016			

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SCALE:	SHEET NO. OF SHEETS	STA. TO STA.
--------	---------------------	--------------

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
3513	2014-05B-RS	COOK	30	4
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT			CONTRACT NO. 60Y90	

Rev 1-04-17