

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
1348	3197A&B&C&D	COOK	35	20
FED. ROAD DIST. NO. 1		ILLINOIS	HIGHWAY PROJECT	

**TRAFFIC SIGNAL LEGEND**

- CONTROLLER
- SERVICE INSTALLATION
- SIGNAL HEAD
- SIGNAL HEAD WITH BACKPLATE
- SIGNAL HEAD, PEDESTRIAN
- SIGNAL POST
- MAST ARM ASSEMBLY AND POLE, STEEL
- MAST ARM ASSEMBLY AND POLE, ALUMINUM
- COMMON TRENCH
- UNIT DUCT
- HANDHOLE
- HEAVY DUTY HANDHOLE
- DOUBLE HANDHOLE
- G.S. CONDUIT IN TRENCH OR PUSHED
- PEDESTRIAN PUSHBUTTON DETECTOR
- DETECTOR LOOP
- SIDEWALK REM. & REP.
- CONC. MED. SURF. REM. & REP.



60721

SPECIAL NOTE: ALL TRENCH AND EXCAVATION SHALL BE SODDED.

115 SQ. FT. SIDEWALK REM.  
115 SQ. FT. PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH  
SIDEWALK REM. & REP. QUANTITIES WILL BE PAID FOR UNDER  
ROADWAY WORK.

LIMIT OF RESURFACING

2-CENTERED RADIUS  
R1=30'; R2=80'; O=4'

EXISTING R.O.W.

SIDEWALK REM. & REP. QUANTITIES WILL BE PAID FOR UNDER ROADWAY WORK.

**REPLACE ALL DETECTOR LOOPS AS SHOWN**

(WITHIN THE RESURFACING LIMITS)

CODE NO.	QUANTITY	LIMIT	ITEM
88600600	360'	Foot	Detector Loop Replacement

**NOTE:**

THIS PLAN IS FOR THE PURPOSE OF REPLACING  
THE DETECTOR LOOPS ONLY. ALL OTHER INFORMATION  
SHOWN IS NOT RELATED AND WILL BE DISREGARDED.

ILLINOIS DEPARTMENT OF TRANSPORTATION

**DETECTOR LOOP REPLACEMENT**

**DEVON AVENUE @ GREENWOOD AVENUE**

REVISIONS	
NAME	DATE

SCALE: VERT.  
HORIZ.  
DATE 9-10-99

DRAWN BY  
DESIGNED BY  
CHECKED BY

