

SUMMARY OF QUANTITIES			URBAN TOTAL QUANTITIES	CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT		22ND STREET I000				
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	22	22				
40600300	AGGREGATE (PRIME COAT)	TON	107	107				
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	10	10				
40600895	CONSTRUCTING TEST STRIP	EACH	1	1				
40600980	BITUMINOUS SURFACE REMOVAL - BUTT JOINT	SQ YD	1651	1651				
40601000	BITUMINOUS REPLACEMENT OVER PATCHES	TON	65	65				
42001300	PROTECTIVE COAT	SQ YD	534	534				
44000103	BITUMINOUS REMOVAL OVER PATCHES 3/4"	SQ YD	740	740				
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	200	200				
44201753	CLASS D PATCHES, TYPE II, 9 INCH	SQ YD	425	425				
44201757	CLASS D PATCHES, TYPE III, 9 INCH	SQ YD	105	105				
44201759	CLASS D PATCHES, TYPE IV, 9 INCH	SQ YD	60	60				
55039700	STORM SEWERS TO BE CLEANED	FOOT	1500	1500				
60252800	CATCH BASINS TO BE RECONSTRUCTED	EACH	1	1				
60257900	MANHOLES TO BE RECONSTRUCTED	EACH	9	9				
60258200	MANHOLES TO BE RECONSTRUCTED WITH NEW TYPE 1 FRAME, CLOSED LID	EACH	2	2				
60300310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	51	51				
60404805	FRAMES AND GRATES, TYPE 11V	EACH	9	9				
60404950	FRAMES AND GRATES, TYPE 24	EACH	10	10				
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	4	4				
67100100	MOBILIZATION	L SUM	1	1				
70102630	TRAFFIC CONTROL AND PROTECTION, STANDARD 701601	L SUM	1	1				
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1				
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	6456	6456				
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	3050	3050				
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	19028	19028				

SUMMARY OF QUANTITIES			URBAN TOTAL QUANTITIES	CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT		22ND STREET I000				
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	17606	17606				
70300250	TEMPORARY PAVEMENT MARKING - LINE 8"	FOOT	356	356				
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	2640	2640				
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	1920	1920				
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	27187	27187				
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	1525	1525				
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	9514	9514				
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	8803	8803				
* 78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	178	178				
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	1320	1320				
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	960	960				
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	595	595				
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	595	595				
* 88600600	DETECTOR LOOP REPLACEMENT	FOOT	3022	3022				
X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	85	85				
X4066426	BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "D", N70	TON	4590	4590				
X4067100	POLYMERIZED LEVELING BINDER (MACHINE METHOD), SUPERPAVE, IL-4.75, N50	TON	2300	2300				
X4409410	BITUMINOUS SURFACE REMOVAL 2 1/4"	SQ YD	53210	53210				
Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	83	83				

* SPECIALTY ITEMS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES
22ND STREET

10/22/2004 10:00:00 AM