

62701

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
			COOK	3
FED. ROAD DIST. NO. 1	ILLINOIS	HIGHWAY PROJECT		

CONTRACT NO. ....

100% STATE

100% STATE

SUMMARY OF QUANTITIES			URBAN		CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT	TOTAL QUANTITIES						
			<b>1000-2A</b>						
<b>20201006</b>	<b>GRADING &amp; SHAPING SHOULDERS</b>	<b>UNIT</b>	<b>22</b>	<b>22</b>					
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	60	60					
40600300	AGGREGATE (PRIME COAT)	TON	300	300					
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	8	8					
40600895	CONSTRUCTING TEST STRIP	EACH	3	3					
40600980	BITUMINOUS SURFACE REMOVAL - BUTT JOINT	SO YD	1486	1486					
40601000	BITUMINOUS REPLACEMENT OVER PATCHES	TON	2200	2200					
42001300	PROTECTIVE COAT	SO YD	220	220					
42300400	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH	SO YD	150	150					
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SO FT	300	300					
44000007	BITUMINOUS SURFACE REMOVAL 2"	SO YD	43,000	43,000					
44000120	BITUMINOUS REMOVAL OVER PATCHES 5"	SO YD	7340	7340					
44000200	DRIVEWAY PAVEMENT REMOVAL	SO YD	150	150					
44000600	SIDEWALK REMOVAL	SO FT	300	300					
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	1530	1530					
44201749	CLASS D PATCHES, TYPE I, 9 INCH	SO YD	229	229					
44201753	CLASS D PATCHES, TYPE II, 9 INCH	SO YD	2071	2071					
44201757	CLASS D PATCHES, TYPE III, 9 INCH	SO YD	765	765					
44201759	CLASS D PATCHES, TYPE IV, 9 INCH	SO YD	940	940					
<b>48101200</b>	<b>AGGREGATE SHOULDERS TY. B</b>	<b>TON</b>	<b>55</b>	<b>55</b>					
60251740	CATCH BASINS TO BE ADJUSTED WITH NEW TYPE 24 FRAME AND GRATE	EACH	10	10					
60252800	CATCH BASINS TO BE RECONSTRUCTED	EACH	3	3					
60300105	FRAMES AND GRATES TO BE ADJUSTED	EACH	5	5					
<del>60300205</del>	<del>FRAMES AND GRATES TO BE ADJUSTED (SPECIAL)</del>	<del>EACH</del>	<del>82</del>	<del>82</del>					
60300310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	114	114					
60406100	FRAMES AND LIDS, TYPE I, CLOSED LID	EACH	14	14					
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6					
67100100	MOBILIZATION	L SUM	1	1					
70102630	TRAFFIC CONTROL AND PROTECTION, STANDARD 701601	L SUM	1	1					

SUMMARY OF QUANTITIES			URBAN		CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT	TOTAL QUANTITIES						
			<b>1000-2A</b>						
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1	1					
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1					
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1	1					
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	30	30					
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	20400	20400					
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SO FT	700	700					
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	45000	45000					
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	3920	3920					
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	3300	3300					
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	925	925					
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SO FT	1295	1295					
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SO FT	700	700					
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	45000	45000					
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	3920	3920					
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	3300	3300					
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	925	925					
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	2200	2200					
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	206	206					
* 88600600	DETECTOR LOOP REPLACEMENT	FOOT	3002	3002					
X0321020	PORTLAND CEMENT CONCRETE SURFACE REMOVAL (COLD MILLING) VARIABLE DEPTH	SO YD	5965	5965					
X0322256	TEMPORARY INFORMATION SIGNING	SO FT	257	257					
X4066426	BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "D", N70	TON	850	850					

REVISIONS	
NAME	DATE

Rev.

ILLINOIS DEPARTMENT OF TRANSPORTATION  
SUMMARY OF QUANTITIES  
**CENTRAL ROAD**  
**BUSSE RD. TO WC RR**

PLOT DATE: 04/16/2004

04/16/2004 10:38:18 AM