

F.A.T. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
90	0102.5-1	COOK	62	3
FED. ROAD DIST. NO. 1		ILLINOIS	HIGHWAY PROJECT	
62794				

SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE						SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE					
CODE NO	ITEM	UNIT	URBAN TOTAL QUANTITIES	ROADWAY 100% STATE I000-2A					CODE NO	ITEM	UNIT	URBAN TOTAL QUANTITIES	ROADWAY 100% STATE I000-2A				
* X0324666	REMOVE AND REINSTALL SURVEILLANCE CABINET	EACH	1	1					* 63100045	TRAFFIC BARRIER TERMINAL, TYPE 2	EACH	1	1				
20200100	EARTH EXCAVATION	CU YD	798	798					* 63100089	TRAFFIC BARRIER TERMINAL, TYPE 6B	EACH	1	1				
20400800	FURNISHED EXCAVATION	CU YD	113	113					* 63100167	TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (TANGENT)	EACH	2	2				
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	4847	4847					67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6				
25000210	SEEDING, CLASS 2A	ACRE	1	1					67100100	MOBILIZATION	L SUM	1	1				
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	90	90					70300100	SHORT-TERM PAVEMENT MARKING	FOOT	520	520				
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	90	90					70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	2890	2890				
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	90	90					70300230	TEMPORARY PAVEMENT MARKING - LINE 5"	FOOT	1700	1700				
25100630	EROSION CONTROL BLANKET	SQ YD	4847	4847					70300250	TEMPORARY PAVEMENT MARKING - LINE 8"	FOOT	950	950				
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	235	235					70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	1015	1015				
28000300	TEMPORARY DITCH CHECKS	EACH	7	7					70300520	PAVEMENT MARKING TAPE, TYPE III 4"	FOOT	3175	3175				
28000500	INLET AND PIPE PROTECTION	EACH	2	2					70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	3500	3500				
28000510	INLET FILTERS	EACH	2	2					70400100	TEMPORARY CONCRETE BARRIER	FOOT	1550	1550				
31101400	SUB-BASE GRANULAR MATERIAL, TYPE B 6"	SQ YD	2860	2860					* 72000300	SIGN PANEL - TYPE 3	SQ FT	2501	2501				
35400500	PORTLAND CEMENT CONCRETE BASE COURSE WIDENING 10"	SQ YD	1030	1030					* 72400330	REMOVE SIGN PANEL - TYPE 3	SQ FT	2100	2100				
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	1.2	1.2					** 72700100	STRUCTURAL STEEL SIGN SUPPORT - BREAKAWAY	POUND	1220	1220				
40600300	AGGREGATE (PRIME COAT)	TON	5.8	5.8					* 73400100	CONCRETE FOUNDATIONS	CU YD	4	4				
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	0.3	0.3					* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	2890	2890				
40600980	BITUMINOUS SURFACE REMOVAL - BUTT JOINT	SQ YD	11	11					* 78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	950	950				
44000900	BITUMINOUS CONCRETE REMOVAL	SQ YD	5	5					* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	1015	1015				
44001980	CONCRETE BARRIER REMOVAL	FOOT	35	35					78002120	PREFORMED PLASTIC PAVEMENT MARKING, TYPE A - LINE 5"	FOOT	1700	1700				
44004250	PAVED SHOULDER REMOVAL	SQ YD	2050	2050					* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	198	198				
44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT	FOOT	3214	3214					* 78200410	GUARDRAIL MARKERS, TYPE A	EACH	8	8				
48101200	AGGREGATE SHOULDERS, TYPE B	TON	80	80					* 78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	2	2				
48202800	BITUMINOUS SHOULDERS SUPERPAVE 10"	SQ YD	1830	1830					78300100	PAVEMENT MARKING REMOVAL	SQ FT	3200	3200				
55039700	STORM SEWERS TO BE CLEANED	FOOT	100	100													
60100060	CONCRETE HEADWALL FOR PIPE DRAINS	EACH	3	3													
60107600	PIPE UNDERDRAINS 4"	FOOT	900	900													
* 63000000	STEEL PLATE BEAM GUARD RAIL, TYPE A	FOOT	137.5	137.5													

* SPECIALTY ITEMS
** SF7Y-3C

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES
I-90 @ I-190 RAMP

PLOT DATE: 10/27/2004

10:04:09 10/27/2004